

POOR LEGIBILITY

**PORTIONS OF THIS DOCUMENT
MAY BE UNREADABLE, DUE TO
THE QUALITY OF THE
ORIGINAL**



JAN 24 1990

4WD-SISB

1010 BENTLEY STREET, NE
ATLANTA, GEORGIA 30346

Mr. John Taylor, Chief
Land Protection Branch
Georgia Department of Natural Resources
205 Butler Street, SW
Atlanta, Georgia 30334

RE: NFRAP GEORGIA SITES

Dear Mr. Taylor:

This is to inform you that the Georgia CERCLIS sites listed below have been assigned No Further Remedial Action Planned (NFRAP) designations. The reason for the designations are the low Preliminary Hazardous Ranking System (HRS) scores calculated for each of the sites.

Please be advised that the NFRAP designations are based on information currently available and conditions and policies that currently exist.

1. GAD000827873 American Metals Company, Inc.
2. GAD980559405 Koppers Company, Garden City Plant

It is possible that in the future our investigation of a site may be reactivated if new information or policies warrant such an action.

Should you have any questions, please contact me at (404) 347-5065.

Sincerely,

Mario E. Villamarzo
Georgia Project Officer
Site Assessment Section

cc: Murray Warner, NUS

YELLOW



1927 LAKESIDE PARKWAY
SUITE 614
TUCKER, GEORGIA 30084
404-938-7710

C-586-5-9-204

May 31, 1989

~~STATE~~
EPA

Mr. A.R. Hanke
Site Investigation and Support Branch
Waste Management Division
Environmental Protection Agency
345 Courtland Street, N. E.
Atlanta, Georgia 30365

COMPLETE
ENG.

[Signature]
NFRAP 1-18-90

Subject: Screening Site Inspection, Phase I
American Metals Company, Inc.
Marietta, Cobb County, Georgia
EPA No. GAD000827873
TDD No. F4-8904-02

1293

received
MAY 31 1989
SISB/SAR

Dear Mr. Hanke:

FIT 4 conducted a screening site inspection, phase I, at American Metals Company, Inc. in Marietta, Cobb County, Georgia. The inspection included a review of EPA and state file material, completion of a target survey, and a drive-by reconnaissance of the facility.

The American Metals Company facility, which is located at 1150 Marietta Industrial Drive NE, paints rolls of steel sheeting. The plant is located in an industrial area on the north side of Marietta (Ref. 1). The facility is not fenced (Ref. 2).

The facility began operations in 1969 as Southcoats. The plant was sold in 1975 and operated as Prior Coated Metals, Inc. The facility was sold again in 1980 and operated as American Metals Company, Inc. (Ref. 1). The plant currently operates as Metal Coaters of Georgia (Ref. 2). The painting process includes uncoiling steel rolls, a caustic wash to remove oil from the metal, a water rinse, an iron phosphate pretreatment, another water rinse, a rinse in a weak solution of chromic acid, application of paint (if the prime coat contains chrome, the paint is ovenbaked), recoiling of metal, and packaging for shipment. The coils may be cut after coating (Ref. 1, attachment 2).

The paint rollers are cleaned with solvents in a self-contained washer. This results in the generation of about 80 drums of spent solvents every 90 days. The spent solvents are sent to Arivec Chemicals, a recycler. All other waste is processed at the plant water-treatment system. Water from the treatment system is discharged to the city sewer. During a 1985 inspection, the treatment system was not functioning, but it was expected to be operative within 6 weeks. Sludge from the treatment system contains paint waste, solvents and caustics and is considered hazardous. Also, the facility generates waste oil from plant fork lifts. The 1985 inspection found seven drums of unlabeled and uncovered drums of sludge that had been stored for over 90 days. As a result, a notice of violation was to be issued to the facility (Ref 1, attachment 3). No information is available concerning waste disposal methods prior to 1980 (Ref. 1).

The facility filed a RCRA Part A application. The application was withdrawn in 1983 and the facilities status was changed to that of generator (Ref. 1, attachment 2).

Mr. A.R. Hanke
Environmental Protection Agency
TDD No. F4-8904-02
May 31, 1989 - page two

American Metals is located within the Piedmont Physiographic Province (Ref. 3, pp. 8, 11, 22). This area is underlain by a complex of metamorphic and igneous rocks that have been described by various geologists as several formations and unnamed mappable units. Specifically, the facility is underlain by the Laura Lake mafic complex, which is the largest intrusive-extrusive complex in the Atlanta region (Ref. 3, p. 44). Individual rock units range in thickness from less than 10 feet to more than 10,000 feet. Regional stresses have warped the rocks into complex folds and refolded folds, and the sequence has been injected by igneous plutons and dikes and broken by faults (Ref. 4, p. 7). The Chattahoochee fault, a large northeast-southwest trending thrust fault, lies 5 miles north of the facility (Ref. 4, plate 1). The climate of this area is temperate, and the annual total precipitation is 48 inches, and the total evaporation is 41 inches annually for a net available recharge of 7 inches annually (Ref. 5).

The large number of rock types in the area and their varied outcrop patterns and distributions greatly complicate the occurrence and availability of groundwater in the area. Groundwater in this vicinity occupies joints, fractures, and other secondary openings in bedrock and pore spaces in the overlying mantle of residual material. The size, spacing, and interconnection of these secondary openings differs greatly from one type of rock to another and with depth below land surface. Water occurrence in this crystalline rock aquifer is controlled by these secondary openings. No confining layers are present; therefore, depth to the water table is highly variable in this unconfined aquifer system (Ref. 4, pp. 7, 9). Reportedly, wells located in this rock type range in depth from 35 to 2175 feet with an average of 294 feet. Yields range from 20 to 275 gpm, averaging 56 gpm (Ref. 4, plate 1). Reportedly, a well 2.3 miles west of the facility, identified as the closest well, is drilled to a depth of 180 feet and yields 30 gpm (Ref. 4, p. 96).

All potable water needs of Cobb County are served by municipal water systems. Surface water supplies the system's needs. The intakes are located at Lake Allatoona and on the Chattahoochee River upgradient of the American Metals facility (Refs. 6, 7).


Surface water runoff from the facility trends southeast overland for 0.4 mile before entering Sope Creek. The creek trends southeast for 9.6 miles before entering the Chattahoochee River, which continues south for the remainder of the 15-mile migration pathway (Ref. 6). No surface water intakes are located along this route (Ref. 8). There is recreational fishing in all of these waters (Ref. 9). Although the ranges of some endangered or threatened species include the state of Georgia, no critical habitats are designated in Cobb County (Ref. 10).

Based on the results of this evaluation and the attached reference material, FIT 4 recommends that no further remedial action be conducted at this facility.

Very truly yours,


Geoffrey Carton
Project Manager

Approved



GC/gwn

Enclosures ()

cc: Mario Villamarzo

REFERENCES

1. Potential Hazardous Waste Site Preliminary Assessment (EPA Form 2070-12) and attachments for American Metals Company, Inc. Filed by Steve Walker, Georgia Department of Natural Resources, June 17, 1985.
2. NUS Field Logbook No. F4-1347 for American Metals Co., Inc., TDD No. F4-8904-02. Documentation of facility reconnaissance, April 12, 1989.
3. K.I. McConnell and C.E. Abrams, Geology of the Greater Atlanta Region: Georgia Geologic Survey Bulletin No. 96, (Georgia Geologic Survey, 1984).
4. C.W. Cressler, C.J. Thurmond, and W.G. Hester, "Ground Water in the Greater Atlanta Region, "Information Circular No. 63, (Atlanta, Georgia: Georgia Geologic Survey, 1983).
5. U.S. Department of Commerce, Climatic Atlas of the United States, (Washington D.C.: GPO, June 1968) Reprint: 1983, National Oceanic and Atmospheric Administration.
6. U.S. Geological Survey, 7.5 minute series Topographic Quadrangle Maps of Georgia: Kennesaw 1956 (Photorevised (PR) 1985), Marietta 1954 (PR 1983), Mountain Park 1956 (PR 1985), Sandy Springs 1955 (PR 1983), scale 1:24,000.
7. Jim Smith, Design, Cobb County Water System, telephone conversation with Geoffrey Carton, NUS Corporation, February 9, 1989. Subject: Water supply in Cobb County.
8. Environmental Protection Division, Georgia Department of Natural Resources, "Water Availability & Use: Chattahoochee River Basin," 1984.
9. Kris Martin, Georgia Department of Natural Resources, telephone conversation with Geoffrey Carton, NUS Corporation, February 8, 1989. Subject: Fishing in Cobb and Dekalb Counties.
10. U.S. Fish and Wildlife Service, Endangered and Threatened Species of the Southeastern United States, (Atlanta, Georgia: 1988).

RECONNAISSANCE CHECKLIST FOR HRS2 CONCERNS

Instructions: Obtain as much "up front" information as possible prior to conducting fieldwork. Complete the form in as much detail as you can, providing attachments as necessary. Cite the source for all information obtained.

Site name: American Metals Company, Inc
City, County, State: Marietta, Cobb County, Georgia
EPA ID No.: GAD 000827873
Person responsible for form: G. Carter
Date: 5/19/89

Air Pathway

Describe any potential air emission sources onsite:

None known

Identify any sensitive environments within 4 miles:

Identify the maximally exposed individual (nearest residence or regularly occupied building - workers do count): workers at the facility

Groundwater Pathway

Identify any areas of karst terrain:

N/A

Identify additional population due to consideration of wells completed in overlying aquifers to the

AOC: None

Do significant targets exist between 3 and 4 miles from the site?

No

Is the AOC a sole source aquifer according to Safe Drinking Water Act? (i.e. is the site located in Dade, Broward, Volusia, Putnam, or Flagler County, Florida)

No

Surface Water Pathway

Are there intakes located on the extended 15-mile migration pathway?

No

Are there recreational areas, sensitive environments, or human food chain targets (fisheries) along the extended pathway? yes, recreational fishing.

Onsite Exposure Pathway

Is there waste or contaminated soil onsite at 2 feet below land surface or higher?

unknown

Is the site accessible to non-employees (workers do not count)?

yes, not fenced.

Are there residences, schools, or daycare centers onsite or in close proximity?

No


Are there barriers to travel (e.g., a river) within one mile?

No



Potential Hazardous Waste Site

Site Inspection Report





Site Inspection Report



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART I - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION
01 STATE: GA 02 SITE NUMBER: 000827873

II. SITE NAME AND LOCATION

01 SITE NAME: Americap Metals Company, Inc.
02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER: 1150 Marietta Industrial Drive, NE
03 CITY: Marietta
04 STATE: GA 05 ZIP CODE: 06 COUNTY: Cobb
07 COUNTY CODE: 08 LONG: 09 LAT: 10 TYPE OF OWNERSHIP: ☒ A PRIVATE ☐ B FEDERAL ☐ C STATE ☐ D COUNTY ☐ E MUNICIPAL ☐ F OTHER ☐ G UNKNOWN

III. INSPECTION INFORMATION

01 DATE OF INSPECTION: 04.12.89
02 SITE STATUS: ☒ ACTIVE ☐ INACTIVE
03 YEARS OF OPERATION: 1969 - Present
04 AGENCY PERFORMING INSPECTION: ☒ A EPA ☒ B EPA CONTRACTOR NUS Corp ☐ C MUNICIPAL ☐ D MUNICIPAL CONTRACTOR ☐ E STATE ☐ F STATE CONTRACTOR ☐ G OTHER

05 CHIEF INSPECTOR: Mary McDonald
06 TITLE: Env. Scientist
07 ORGANIZATION: NUS
08 TELEPHONE NO: (404) 938-7710


09 OTHER INSPECTORS: Ron Wilde
10 TITLE: Biologist
11 ORGANIZATION: NUS
12 TELEPHONE NO: (404) 938-7710

13 SITE REPRESENTATIVES INTERVIEWED
14 TITLE
15 ADDRESS
16 TELEPHONE NO

17 ACCESS CODE BY: ☐ PERMISSION ☐ WARRANT
18 TIME OF INSPECTION: 1330
19 WEATHER CONDITIONS: Partly Cloudy 65°F

IV. INFORMATION AVAILABLE FROM

01 CONTACT: Mario Villamarzo
02 EPA REGION: EPA Region 4
03 TELEPHONE NO: (404) 347-5065
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM: Geoff Carton
05 AGENCY: FIT 4
06 ORGANIZATION: NUS Corp
07 TELEPHONE NO: (404) 938-7710
08 DATE: 05.19.89



<input checked="" type="checkbox"/> A TOXIC	<input type="checkbox"/> E SOLUBLE	<input type="checkbox"/> I HIGHLY VOLATILE
<input type="checkbox"/> B CORROSIVE	<input type="checkbox"/> F INFECTIOUS	<input type="checkbox"/> J EXPLOSIVE
<input type="checkbox"/> C RADIOACTIVE	<input checked="" type="checkbox"/> G FLAMMABLE	<input type="checkbox"/> K REACTIVE
<input checked="" type="checkbox"/> D PERSISTENT	<input type="checkbox"/> H IRRITABLE	<input type="checkbox"/> L INCOMPATIBLE
		<input type="checkbox"/> M NOT APPLICABLE

EPA FORM 2070-13 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1. IDENTIFICATION
01 STATE: GAD 02 SITE NUMBER: 000827873

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

None Documented (N/D) groundwater not used in this area

01 ☐ B SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

N/D No surface water intakes in area

01 ☐ C CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

N/D

01 ☐ D FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

N/D

01 ☐ E DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ F CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

N/D

01 ☐ G DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

N/D see above

01 ☐ H WORKER EXPOSURE/ILLNESS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

N/D

01 ☐ I POPULATION EXPOSURE/ILLNESS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

N/D



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1. IDENTIFICATION	
01 STATE	02 SITE NUMBER
GA	00082873

II. HAZARDOUS CONDITIONS AND INCIDENTS Continued

01 ☐ J DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

N/D

01 ☐ K DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION INCLUDE NATURE OF OCCURRENCE

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

N/D

01 ☐ L CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

N/D

01 ☐ M UNSTABLE CONTAINMENT OF WASTES
Leaking drums, Spilling drums, Leaking drums
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

N/D

01 ☐ N DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

N/D

01 ☐ O CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED

Waste water from facility is discharged to sewer

01 ☐ P ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

N/D

06 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

N/D

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION AND QUALITY RELIABILITY & D. AND FOR SOURCE CREDITS, REFERENCE

EPA + State files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

1. IDENTIFICATION
01 STATE **GAD** 02 SITE NUMBER **000827873**

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED <small>Check all that apply</small>	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE <small>Specify</small>				
<input type="checkbox"/> H. LOCAL <small>Specify</small>				
<input type="checkbox"/> I. OTHER <small>Specify</small>				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL <small>Check all that apply</small>	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT <small>Check all that apply</small>	05 OTHER
<input type="checkbox"/> A. SURFACE IMPONDEMENT			<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input checked="" type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER <small>Specify</small>	
<input type="checkbox"/> I. OTHER <small>Specify</small>				

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES Check all that apply

☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☐ D. INADEQUATE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DRUMS, LINES, BARRIERS, ETC.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☐ YES ☐ NO
02 COMMENTS

VI. SOURCES OF INFORMATION Check all sources consulted, e.g., MSDS files, permit records, reports

EPA & state files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GAD 000B27873

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY
Check as appropriate

	SURFACE	WELL
COMMUNITY	A <input checked="" type="checkbox"/>	B <input type="checkbox"/>
NON-COMMUNITY	C <input type="checkbox"/>	D <input type="checkbox"/>

02 STATUS

ENDANGERED	AFFECTED	MONITORED
A <input type="checkbox"/>	B <input type="checkbox"/>	C <input type="checkbox"/>
D <input type="checkbox"/>	E <input type="checkbox"/>	F <input type="checkbox"/>

03 DISTANCE TO SITE

Not on drainage
path
A. _____ (mi)
B. _____ (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY Check one

☐ A ONLY SOURCE FOR DRINKING ☐ B DRINKING
Other sources available
COMMERCIAL, INDUSTRIAL, IRRIGATION
No other water required elsewhere
☐ C COMMERCIAL, INDUSTRIAL, IRRIGATION
Limited other sources available
☒ D NOT USED; UNUSABLE

02 POPULATION SERVED BY GROUND WATER _____

03 DISTANCE TO NEAREST DRINKING WATER WELL _____ (mi)

04 DEPTH TO GROUNDWATER

_____ (ft)

05 DIRECTION OF GROUNDWATER FLOW

06 DEPTH TO AQUIFER
OF CONCERN

_____ (ft)

07 POTENTIAL YIELD
OF AQUIFER

_____ (gpm)

08 SOLE SOURCE AQUIFER

☐ YES ☒ NO

09 DESCRIPTION OF WELLS (including depth, construction, and whether access is convenient and adequate)

10 RECHARGE AREA

☐ YES COMMENTS
☐ NO

11 RECHARGE AREA

☐ YES COMMENTS
☐ NO

IV. SURFACE WATER

01 SURFACE WATER USE Check one

☒ A RESERVOIR, RECREATION
DRINKING WATER SOURCE ☐ B IRRIGATION, ECONOMICALLY
IMPORTANT RESOURCES ☐ C COMMERCIAL, INDUSTRIAL ☐ D NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:

Sage Creek
Chattahoochee River

AFFECTED

DISTANCE TO SITE

0.4 (mi)
10 (mi)
_____ (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE

TWO (2) MILES OF SITE

THREE (3) MILES OF SITE

A. _____
NO. OF RESIDING

B. _____
NO. OF RESIDING

C. _____
NO. OF RESIDING

02 DISTANCE TO NEAREST POPULATION

_____ (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

04 DISTANCE TO NEAREST OFF-SITE BUILDING

_____ (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide number of residents of nearest off-site population within vicinity of site, e.g., 1000, 10000, 100000, 1000000, etc.)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

IDENTIFICATION
01 STATE 02 SITE NUMBER
GA0 000827873

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE Check one

☐ A. $10^{-8} - 10^{-6}$ cm/sec ☒ B. $10^{-6} - 10^{-4}$ cm/sec ☐ C. $10^{-4} - 10^{-2}$ cm/sec ☐ D. GREATER THAN 10^{-2} cm/sec

02 PERMEABILITY OF BEDROCK Check one

☐ A. IMPERMEABLE ☐ B. RELATIVELY IMPERMEABLE ☐ C. RELATIVELY PERMEABLE ☐ D. VERY PERMEABLE
(Less than 10^{-8} cm/sec) $10^{-8} - 10^{-6}$ cm/sec $10^{-6} - 10^{-4}$ cm/sec Greater than 10^{-4} cm/sec

03 DEPTH TO BEDROCK

_____ (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

_____ (ft)

05 SOIL pH

06 NET PRECIPITATION

_____ (in)

07 ONE YEAR 24 HOUR RAINFALL

_____ (in)

08 SLOPE

SITE SLOPE

DIRECTION OF SITE SLOPE

TERRAIN AVERAGE SLOPE

09 FLOOD POTENTIAL

SITE IS IN _____ YEAR FLOODPLAIN

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS: 1 mile minimum

ESTUARINE

OTHER

A. _____ (mi)

B. _____ (mi)

12 DISTANCE TO CRITICAL HABITAT for endangered species

None

(mi)

ENDANGERED SPECIES: _____

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

OR SITE

A. _____ (mi)

B. _____ (mi)

C. _____ (mi)

D. _____ (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Re: Five water bodies on the facility flows generally south overland 4
with before entering Five Creek. The creek trends south east for 0.5 miles
before entering the Chattahoochee River which continues south for the
remainder of the 10-mile migration pathway. No surface water bodies
are located along this route. There is recreational fishing and
of these waters.

VII. SOURCES OF INFORMATION (See General Information, A.C. and B.C. sections of this report)

EPA & state files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GAD 000827873

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>NUS CORP</u>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>NUS CORP</u>

V. OTHER FIELD DATA COLLECTED

VI. SOURCES OF INFORMATION

EPA + State files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GAD 000027873

II. CURRENT OWNERS

01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
Metal Coaters of Georgia															
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				10 STREET ADDRESS (P.O. Box, Apt. #, etc.)				11 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				12 CITY				13 STATE 14 ZIP CODE			
01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				10 STREET ADDRESS (P.O. Box, Apt. #, etc.)				11 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				12 CITY				13 STATE 14 ZIP CODE			
01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				10 STREET ADDRESS (P.O. Box, Apt. #, etc.)				11 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				12 CITY				13 STATE 14 ZIP CODE			
01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				10 STREET ADDRESS (P.O. Box, Apt. #, etc.)				11 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				12 CITY				13 STATE 14 ZIP CODE			
01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				10 STREET ADDRESS (P.O. Box, Apt. #, etc.)				11 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				12 CITY				13 STATE 14 ZIP CODE			

III. PREVIOUS OWNERS (List most recent first)

01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
American Metals Co, Inc															
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				05 STREET ADDRESS (P.O. Box, Apt. #, etc.)				06 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				08 CITY				09 STATE 10 ZIP CODE			
01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
Prior Coated Metals															
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				05 STREET ADDRESS (P.O. Box, Apt. #, etc.)				06 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				08 CITY				09 STATE 10 ZIP CODE			
01 NAME				02 D-B NUMBER				03 NAME				04 D-B NUMBER			
Southcoats															
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)				04 SIC CODE				05 STREET ADDRESS (P.O. Box, Apt. #, etc.)				06 SIC CODE			
05 CITY				06 STATE 07 ZIP CODE				08 CITY				09 STATE 10 ZIP CODE			

V. SOURCE OF INFORMATION (List sources of information, e.g., EPA file, owner company records)

EPA + state files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

GAD 000027073

II. CURRENT OPERATOR

(Provide information for current operator)

OPERATOR'S PARENT COMPANY

(Provide information)

01 NAME		02 D-S NUMBER		10 NAME		11 D-S NUMBER	
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)		04 SEC CODE		12 STREET ADDRESS (P.O. Box, Apt. #, etc.)		13 SEC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					

III. PREVIOUS OPERATOR(S)

(List most recent first; provide only if different from current)

PREVIOUS OPERATORS' PARENT COMPANIES

(Provide information)

01 NAME		02 D-S NUMBER		10 NAME		11 D-S NUMBER	
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)		04 SEC CODE		12 STREET ADDRESS (P.O. Box, Apt. #, etc.)		13 SEC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D-S NUMBER		10 NAME		11 D-S NUMBER	
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)		04 SEC CODE		12 STREET ADDRESS (P.O. Box, Apt. #, etc.)		13 SEC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D-S NUMBER		10 NAME		11 D-S NUMBER	
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)		04 SEC CODE		12 STREET ADDRESS (P.O. Box, Apt. #, etc.)		13 SEC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION

(Provide names, addresses, and phone numbers of sources of information)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GAD 000827873

II. ON-SITE GENERATOR

01 NAME	02 D-S NUMBER		
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME	02 D-S NUMBER	01 NAME	02 D-S NUMBER		
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D-S NUMBER	01 NAME	02 D-S NUMBER		
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D-S NUMBER	01 NAME	02 D-S NUMBER		
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE
01 NAME	02 D-S NUMBER	01 NAME	02 D-S NUMBER		
03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, Apt. #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

V. SOURCES OF INFORMATION (add copies of references, e.g., MSDS, etc., attach copies, reference)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
GAD 000027873

II. PAST RESPONSE ACTIVITIES

None Known

01 ☐ A. WATER SUPPLY CLOSED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ D. SPILLED MATERIAL REMOVED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ E. CONTAMINATED SOIL REMOVED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ F. WASTE REPACKAGED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ G. WASTE DISPOSED ELSEWHERE
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ H. ON SITE BURIAL
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ I. IN SITU CHEMICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ J. IN SITU BIOLOGICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ K. IN SITU PHYSICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ L. ENCAPSULATION
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ M. EMERGENCY WASTE TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ N. CUTOFF WALLS
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ O. EMERGENCY DRAIN/SURFACE WATER DIVERSION
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ P. CUTOFF TRENCHES/SLIMP
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Q. SUBSURFACE CUTOFF WALL
04 DESCRIPTION

02 DATE

03 AGENCY



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
GA0 000827873

II. PAST RESPONSE ACTIVITIES Continued

01 <input type="checkbox"/> R BARRIER WALLS CONSTRUCTED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> S CAPPING COVERING 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> T BULK TANKAGE REPAIRED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> U GROUT CURTAIN CONSTRUCTED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> V BOTTOM SEALED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> W GAS CONTROL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> X FIRE CONTROL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Y LEACHATE TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Z AREA EVACUATED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 1 ACCESS TO SITE RESTRICTED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 2. POPULATION RELOCATED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 3. OTHER REMEDIAL ACTIVITIES 04 DESCRIPTION	02 DATE _____	03 AGENCY _____

III. SOURCES OF INFORMATION (City, County, State, U.S., State, Site, Agency, Other, Other)

EPA & state files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

1. IDENTIFICATION

01 STATE 02 SITE NUMBER
GAD 000827873

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY ENFORCEMENT ACTION ☒ YES ☐ NO

02 DESCRIPTION OF FEDERAL STATE LOCAL REGULATORY/ENFORCEMENT ACTION

Notice of violation was called for based on 1/16/85 inspection,
In violation because waste oil had not been classified, storage
over 90 days, drums of waste not properly marked, and
containers not in good condition.

III. SOURCES OF INFORMATION (also attach references, e.g., state files, correspondence, reports)

EPA + state files

Reference 1

*Filed
850627
C.B. Warren*

**PRELIMINARY ASSESSMENT COVER SHEET
AMERICAN METALS COMPANY INC.
GAD000827873**

Operations at this facility began in 1969 under the ownership of Southcoats. In 1975, the plant was sold to Prior Coated Metals, Inc. who operated the facility until it was purchased by the American Metals Co., Inc. in 1980. Since its inception in 1969, the facility has been used to paint rolls of steel sheeting. This facility is presently classified as a generator; its Part A application has been withdrawn.

In a phone conversation on 6/17/85, the facility engineer, Mr. Carl Houser, seemed unsure of hazardous waste handling practices prior to 1980. Since that date, the facility has generated small quantities of waste paint, solvents, caustics and chromic acids. These wastes have been discharged under permit to the local POTW. A wastewater treatment system was operative at one time during the 1970's or early 1980's. The system was apparently cleaned out and the accumulated sludges were drummed. In a conversation on 6/17/85, Frances Hallahan of the Georgia EPD stated that when she visited the site on 1/16/85, several rusty drums containing waste water treatment sludges were located in back of the facility. Ms. Hallahan indicated that the Generator Compliance Unit of the Georgia EPD is requiring the facility to furnish analytical results for the sludge. The facility plans to have a new waste water treatment system in operation by December 1985.

The facility is located in an industrial park adjacent to Marietta, Georgia. The area around the facility is moderately to heavily populated. Surface run-off from the site enters a small lake about 1/4 mile to the south. Ground water is not known to be used in the site area.

The site is assessed a "low" priority for a Site Inspection because information on hazardous waste handling practices prior to 1980 is incomplete.

CSW/mcw020



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GA 0000827873

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) American Metals Company, Inc.		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 1150 Marietta Industrial Drive, NE			
03 CITY Marietta	04 STATE GA	05 ZIP CODE 30062	06 COUNTY Cobb	07 COUNTY CODE 067	08 CONG DIST 07
09 COORDINATES LATITUDE 33° 58' 43.5"		LONGITUDE 084° 32' 16.0"			

10 DIRECTIONS TO SITE (Starting from nearest public road): From Intersection of Hwy. 41 and Allgood Road, proceed north on Hwy 41 and turn right (NE) on 1st road to the right. Proceed 1/4 mile to Web Drive and turn right (east). Proceed for 1,000 yds. and turn left (north) onto Marietta Industrial Drive. The facility is the last building on the right at the end of the road.

III. RESPONSIBLE PARTIES

01 OWNER (if owner) Donn Corporation		02 STREET (Business, mailing, residential) 1000 Crocker Road			
03 CITY West Lake	04 STATE OH	05 ZIP CODE 44145	06 TELEPHONE NUMBER (216) 871-1000		
07 OPERATOR (if known and different from owner)		08 STREET (Business, mailing, residential)			
09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER ()		

13 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE ☐ B. FEDERAL: _____ (Agency name) ☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL
☐ F. OTHER: _____ (Specify) ☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)

☒ A. RCRA 3001 DATE RECEIVED: _____ MONTH DAY YEAR ☐ B. UNCONTROLLED WASTE SITE (RCRA 102(c)) DATE RECEIVED: _____ MONTH DAY YEAR ☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE 02-08-85 <input type="checkbox"/> NO MONTH DAY YEAR		BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input checked="" type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) F. Hallahan CONTRACTOR NAME(S): _____			
02 SITE STATUS (Check one) <input checked="" type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN		03 YEARS OF OPERATION 1969 continuing BEGINNING YEAR ENDING YEAR <input type="checkbox"/> UNKNOWN			

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

caustics
chromic acid
paint sludges
solvents (unspecified)

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

Low - information on hazardous waste handling prior to 1980 is incomplete.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents)

☐ A. HIGH (inspection required promptly) ☐ B. MEDIUM (inspection required) ☒ C. LOW (inspect on time available basis) ☐ D. NONE (no further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT Carl Patton-Plant Supt.	02 CF (Agency Organization) American Metals Company, Inc.	03 TELEPHONE NUMBER (404) 427-9471			
04 PERSON RESPONSIBLE FOR ASSESSMENT Steve Walker	05 AGENCY DNR	06 ORGANIZATION EPD-RAU	07 TELEPHONE NUMBER (404) 656-7404	08 DATE 06-17-85	

J. Smorice



<input checked="" type="checkbox"/> A. TOXIC	<input type="checkbox"/> E. SOLUBLE	<input type="checkbox"/> I. HIGHLY VOLATILE
<input type="checkbox"/> B. CORROSIVE	<input type="checkbox"/> F. INFECTIOUS	<input type="checkbox"/> J. EXPLOSIVE
<input type="checkbox"/> C. RADIOACTIVE	<input checked="" type="checkbox"/> G. FLAMMABLE	<input type="checkbox"/> K. REACTIVE
<input type="checkbox"/> D. PERSISTENT	<input type="checkbox"/> H. IGNITABLE	<input type="checkbox"/> L. INCOMPATIBLE

SPAF-44070-1-1-21



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GA D000827873

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ B. SURFACE WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ C. CONTAMINATION OF AIR
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ E. DIRECT CONTACT
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☒ F. CONTAMINATION OF SOIL
03 AREA POTENTIALLY AFFECTED: 1 - 3
(Acres)

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☒ POTENTIAL ☐ ALLEGED

Hazardous waste handling practices prior to 1980 are unknown.

01 ☐ G. DRINKING WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ H. WORKER EXPOSURE/INJURY
03 WORKERS POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ I. POPULATION EXPOSURE/INJURY
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GA D000827873

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include names of species)

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES

Spills, runoff, standing liquids, leaking drums

03 POPULATION POTENTIALLY AFFECTED: unknown

02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED

04 NARRATIVE DESCRIPTION

Hazardous waste handling practices prior to 1980 are unknown.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

01 ☐ P. ILLEGAL UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: unknown

IV. COMMENTS

In a phone conversation on 6/17/85, Carl Houser (Facility Engineer) seemed uncertain of hazardous waste handling procedures at the site prior to 1980.

V. SOURCES OF INFORMATION (include specific references e.g., state files, sample analysis reports)

Phone conversation on 6/17/85 with the Facility Engineer, Carl Houser -
Memo attached.

Figure 1; Site Location p American Metals Comp., Inc.
Attachment 1




MARIETTA QUADRANGLE

GEORGIA-COBB CO.

QUADRANGLE LOCATION

7.5 MINUTE SERIES (TOPOGRAPHIC)

SCALE 1:24,000



Attachment 2



JOE D. TANNER
Commissioner

Department of Natural Resources

ENVIRONMENTAL PROTECTION DIVISION
270 WASHINGTON STREET S.W.
ATLANTA, GEORGIA 30334

J. LEONARD LEDBETTER
Division Director

FILE COPY September 7, 1983

Mr. Sandor Frecska
Manager, Manufacturing Eng.
Donn Corporation
1000 Crocker Road
Westlake, OH 44145

RE: Request for Facility Status
Changes for American Metals Co.
Marietta, GA GAD000827873

Dear Mr. Frecska:

This will acknowledge receipt of your request for withdrawal of your application for a Hazardous Waste Facility permit.

Based on the information provided, and an inspection made on August 30, 1983, withdrawal of your application is warranted and your permit application has been placed in our inactive files.

As requested, your status has been changed to a generator and your EPA Identification Number has been retained. Storage of waste for less than ninety (90) days requires compliance with 40 CFR 262.34 of Georgia's Rules for Hazardous Waste Management.


Please be advised that withdrawal of your permit application invalidates any variance that you received to continue existing hazardous waste treatment storage or disposal during the permit review process and that based on our concurrence with your withdrawal request, the Federal Environmental Protection Agency will terminate your facility's interim status.

Should you wish to treat, store, or dispose of hazardous waste in the future, it will be necessary that a hazardous waste handling permit be issued, prior to the construction of such facilities, under authority of Section 8 of the Georgia Hazardous Waste Management Act and paragraphs .10 and .11 of Georgia's Rules for Hazardous Waste Management, Chapter 391-3-11.

Mr. Sandor Frecska
Donn Corp.
September 7, 1983
Page 2

If further clarification is needed on this matter, please feel free to contact Ms. Verona Barnes at 404/656-7802.

Sincerely,

A handwritten signature in cursive script, appearing to read "John D. Taylor, Jr.", written in dark ink.

John D. Taylor, Jr., Program Manager
Industrial & Hazardous Waste
Management Program

JDT:vbb:680

cc: James H. Scarbrough
Joe Surowiec
David Cheek
File: American Metals Co. (Y)



Attachment 3

Department of Natural Resources

ENVIRONMENTAL PROTECTION DIVISION

270 WASHINGTON STREET S.W.

ATLANTA, GEORGIA 30334

TRIP REPORT

February 8, 1985

Commissioner

J. LEONARD LEOBETTER

Site Name and Location: American Metals Company, Inc. (4)
1150 Marietta Industrial Drive, N.E.
Marietta, Georgia 30062

Trip By: Frances M. Hallahan *FH*

Accompanied By: None

Date of Trip: January 16, 1985; 1:30 p.m.; cloudy, cold.

Officials Contacted: Mr. Carl H. Patton, Plant Superintendent
(404)427-9471

Mr. Carl Hauser, Facility Engineer

Reference: Complaint #5-136

Comments:

1. Process: This facility paints large rolls of steel sheeting which is then shipped elsewhere for fabrication. They are technically described as a "coil coater". The steel rolls are uncoiled and fed through the following steps:

- a) Caustic wash, which removes the oil coating on the steel
- b) Water rinse
- c) Iron phosphate pre-treatment
- d) Water rinse
- e) Final rinse in a weak solution of chromic acid
- f) Prime and/or finish coat of paint. If the prime coat contains chrome:
- g) Oven bake to cure the paint
- h) Cooled
- i) Re-coiled and packed for shipment
- j) Some coils are cut to smaller sizes after coating

The paint is applied with rollers, so there is no paint overspray waste. Solvents are used to clean the rolls, and about 80 drums of spent solvents are generated every 90 days. These are appropriately manifested as a hazardous waste to Arivec Chemicals.

All washwater, rinses and spent baths, and bottom sludges are fed to the wastewater treatment system. The officials admitted that this system has not been working properly since they located here in 1980. At present, all wastewater treatment is shut down completely, and the waste stream is fed untreated to the city sewer connection. The officials explained that the city is aware of this discharge, and they are allowed to discharge until the wastewater treatment system becomes operative, with in about 6 weeks. This untreated discharge is probably the basis of the complaint by an anonymous employee. The new system will consist of:

FILE COPY

- a) Chrome treatment with sodium metabisulfite
- b) Oil skim
- c) pH adjustment
- d) Clarifier
- e) Filter press
- f) Discharge of effluent to city sewer

The filter press sludge will be hazardous because of the chrome content. The sludge will also be high in zinc hydroxide because the caustic bath draws the zinc from the steel to form zinc hydroxide.

2. Plant Tour

General plant housekeeping was good. The 3-stage washer is self contained, and solvent handling in the paint room is satisfactory, except that the spent solvents are not labelled at the point of generation. At the time of this inspection, a tanker truck from Arivec was in the process of pumping out about 40 drums of paint/solvent waste. These drums were also not labelled and dated. The officials explained that these drums would be used over again to collect more waste. Empty drums of fresh solvent, the iron phosphate, and chrome, are recycled back to suppliers at the time of delivery.

The facility generates about 1 drum every 3 months of waste motor oil from the fork lifts in the plant. We agreed that the oil would be tested for hazardousness.

Inspection of the outside clarifier revealed 7 drums of sludge which were generated when the old wastewater treatment system was in operation. These were unlabelled and uncovered, and officials admitted that they had been accumulating for over 90 days.

3. Wastes Generated:

- a) Spent paint solvents - about 80 drums/3 months
- b) Wastewater treatment sludge - hazardous
- c) oil to be skimmed from wastewater treatment
- d) Waste motor oil.

4. Examination of Paperwork:

Manifests for spent solvents were in order, and reflect shipment within the 90 day period. There is no inspection program for the hazardous wastes, and the facility has no Preparedness and Prevention Plan, Contingency Plan or Personnel Training Program.

Conclusions: Facility is in violation of:

40 CFR 262.11 "Determination", because waste oil has not been identified as hazardous or non-hazardous;

Page Three (3)

TR-American Metals Company, Inc.

40 CFR 262.34(a) "Accumulation Time", because 7 drums of sludge have been stored over 90 days, and because both sludge and paint solvent waste are not marked "Hazardous Waste", and are not marked with beginning dates of accumulation;

40 CFR 262.34(a)(4) "Accumulation Time", because the facility has no Preparedness and Prevention Plan, Contingency Plan, or Personnel Training Program.

40 CFR 265, Subpart I, "Containers", because some containers of hazardous waste are not kept in good condition and are uncovered, and because there is no weekly inspection of containers.

Recommendations and follow-up Required: Send NOV.

Photographs: None

Reviewed By:

George Morris 2-12-25

Attachments: Copy of Complaint

FH:djb:005

cc: Frances Hallahan
Complaint Log #5-136
Howard Barefoot

File: American Metals Co. (R)

Attachment 4

PRELIMINARY ASSESSMENT
TELEPHONE CONVERSATION RECORD

Site Name: Ambridge Metal Recycling Inc. I.D.# 0000000000

Location Address: 1000 Industrial Rd. Ambridge, Pa.

Phone: (412) 417-9471

Contact: Carl Houser Title: Plant Manager

Address: 1000 Industrial Rd. Ambridge, Pa. 15009

Phone: (412) 321-4199

Authority: Section 3012 of CERCLA, Comprehensive Environmental Response, Compensation and Liability Act.

Facility has notified EPA via - RCRA 3001 site is in HWDMS
CERCLA 103c site is in NOTIS

Need Information concerning waste generation and disposal prior to Nov. 19, 1980.

How long has facility been in operation? Since 1971

What kind of wastes were generated and how much?

chlorinated solvents, some waste paint, caustics and small amounts of acid.

Was it disposed on site and where?

"not to my knowledge"

Was it transported offsite and where?

past - unknown, current - all hazardous waste is currently discharged to the local sewer.

Was it treated and how?

past - unknown, current - discharged to POTW

Have there been any past spills? Describe.

"not to my knowledge"

Date of call: 6/17/85 Time: 1:55 p.m.

tf
Steve Walker



LEVEL

NOTEBOOK NO. 311

FJ-1347

American Metals Co., Inc

T.D.D. # F4-59071-02

Marietta, Cobb County, Georgia

Project Manager: Geoff Carter

a product of

J. L. DARLING CORPORATION

TACOMA, WASHINGTON 98421 U.S.A.

LOGBOOK REQUIREMENTS
REVISED - NOVEMBER 29, 1988

NOTE: ALL LANGUAGE SHOULD BE FACTUAL AND OBJECTIVE

1. Record on front cover of the Logbook: TDD No., Site Name, Site Location, Project Manager
2. All entries are made using ink. Draw a single line through errors. Initial and date corrections.
3. Statement of Work Plan, Study Plan, and Safety Plan discussion and distribution to field team with team member signatures.
5. Sign and date each page. Project Manager is to review and sign off on each logbook daily.
6. Document all calibration and pre-operational checks of equipment. Provide serial numbers of equipment used onsite.
7. Provide reference to Sampling Field Sheets for detailed sampling information.
8. Describe sampling locations in detail and document all changes from project planning documents.
9. Provide a site sketch with sample locations and photo locations.
10. Maintain photo log by completing the stamped information at the end of the logbook.
11. If no site representative is on hand to accept the receipt for samples an entry to that effect must be placed in the logbook.
12. Record I.D. numbers of COC and receipt for sample forms used. Also record numbers of destroyed documents.
13. Complete SMO Information in the space provided.

All entries will be made
by myself, Mary McDonald.
All entries will be signed
by the project manager, Geoff
Carton.

Errors will be marked through
and initialed

We the undersigned
understand the scope of
work as stated in the project
work plan:

Mary McDonald
Kenneth Alden

0000004

4/12/89


that may direct the surface
channel another way.
We could not walk around
the property to see the
sprawling high ridge is
moved to a different
location and the high
ridge that is there now
is the low valley high
ridge. The high ridge
is also abandoned.

0000005

High Country

4/12/89

0000000




High Country

0000005


Reference No. 3

GEOLOGY OF THE GREATER ATLANTA REGION

Keith I. McConnell and Charlotte E. Abrams



Department of Natural Resources
Environmental Protection Division
Georgia Geologic Survey



BULLETIN 96

(1958) redefined the ages for the previously mentioned rock units and gave an age of approximately 295 m.y. for the Panoia Granite. Interest in the age of these post-metamorphic intrusive rocks continued into the 1960's, 1970's and 1980's as the methodology of isotopic dating improved and the precision of the age determinations was refined. Although the exact ages for these intrusive bodies varied, the succeeding reports (i.e., Long and others, 1959; Whitney and others, 1976; Dallmeyer, 1978; Atkins and Higgins, 1980; Higgins and Atkins, 1981) essentially confirmed late Paleozoic ages for the post-metamorphic intrusive rocks. The results of investigations into the timing of metamorphism were being reported at the same time as ages for post-metamorphic intrusives. Initial K-Ar work on schists and gneisses in the southern Piedmont by Pinson and others (1957), Kulp and Eckelmann (1961) and Long and others (1959) indicated ages from approximately 350 m.y. to 250 m.y. with a distinct "younging" trend to the southeast from Atlanta. Kulp and Eckelmann (1961) suggested that these ages indicated two periods of regional metamorphism: one at approximately 350 m.y. and the second near 250 m.y. ago. Using the above ages, Hurst (1970) coined the term "hot belt" for the area containing the younger ages. Stonebraker (1973) provided additional K-Ar analyses on samples from traverses across the Brevard zone near Atlanta. Finally, Dallmeyer (1975) indicated that $^{40}\text{Ar}/^{39}\text{Ar}$ ages suggested that the younger age-dates obtained by K-Ar methods are the result of differences in cooling and uplift rates. He suggested an age of 365 m.y. for peak metamorphism of the region described here as southern Piedmont (Dallmeyer, 1975).

Outside of isotopic dating efforts, geologic interest in the southern Piedmont during the late 1950's and 1960's was concentrated around the Stone Mountain Granite. Reports regarding mineralogical variation (Wright, 1966), weathering (Grant, 1963), and intrusion mechanics (Grant, 1969) of the Stone Mountain Granite were published during this time period. Grant (1962) also led a field trip into the Stone Mountain-Lithonia district. The 1970's and early 1980's saw a continuation of geologic interest in the Stone Mountain Granite. Reports on the origin (Whitney and others, 1976) and geochemistry (Atkins and others, 1980b) of the Stone Mountain Granite as well as another field trip guidebook for the area (Grant and others, 1980) were published.

After a gap of over a decade, publication on the stratigraphy and structure of the southern Piedmont resumed in the mid-1960's with the publications on the Brevard zone by Higgins (1966, 1968). In the recent past, reports regarding the various aspects of stratigraphy and structure were published (i.e., Atkins and Higgins, 1978, 1980; Atkins and others, 1980a; Higgins and others, 1980a, 1980b; Higgins and Atkins, 1981; Kline, 1980, 1981).

Much of the preceding geologic information from all of the aforementioned geographic areas was included in the compilation of the 1976 State Geologic Map of Georgia. This map also included unpublished reconnaissance mapping by various geologists (Georgia Geologic Survey, 1976).

STRATIGRAPHY

Introduction

Detailed and reconnaissance geologic mapping has formed the basis on which stratigraphic successions for the Blue Ridge, northern Piedmont and southern Piedmont were developed. Much of this mapping expanded upon earlier reconnaissance mapping by many authors.

In the Blue Ridge, the proposed stratigraphic terminology and correlations are, to some degree, a return to those of C.W. Hayes (1895) in his unpublished report on the Cartersville 30-minute sheet. Although written nearly 100 years ago, Hayes' report on the Cartersville area, particularly the stratigraphic correlations and his interpretation of the relationship between the Corbin Gneiss Complex and its cover rocks, is consistent with our interpretations.

South of the Allatoona fault and north of the Brevard zone, imprecise and over-extended terms such as Ashland and Wedowee are abandoned in favor of two major groups (i.e., New Georgia and Sandy Springs Groups) that are distinguished on the basis of lithology, protolith, and depositional environment. Resolution of a recognizable stratigraphy in the northern Piedmont also has led to the recognition of stratigraphic indicators for massive sulfide and gold deposits (Abrams and McConnell, 1982a).

Southeast of the Brevard fault zone, Higgins and Atkins (1981) defined the Atlanta Group. In this report, we use units defined by Higgins and Atkins, but reinterpret the structural setting, redefining the major structural feature, the Newnan-Tucker synform, as a synformal anticline rather than a synformal syncline as originally proposed (Higgins and Atkins, 1981). The stratigraphic succession used in the Valley and Ridge is after Cressler (1970) and Cressler and others (1979), which were modified from Hayes (1902) and Butts and Gildersleeve (1948).

The following discussion describes in detail only those rock units that are in areas which have undergone substantial revision during this investigation. In this report capitalization of previously defined stratigraphic units follows the original author's usage unless otherwise defined in this text. For a description of all stratigraphic units within the Greater Atlanta Regional area see Appendix A of this report.

Stratigraphy of the Valley and Ridge

Rocks ranging in age from Lower Cambrian(?) to Pennsylvanian are present in the Valley and Ridge portion of the Greater Atlanta Regional Map. Our work in the Valley and Ridge portion of the Greater Atlanta Region was directed at an area in the immediate vicinity of Cartersville (Fig. 2). For this reason we have limited our discussion of Valley and Ridge stratigraphy to rocks in that area. This means that only Lower Cambrian rocks (Chilhowee through Rome Formations) are discussed. The reader is referred to Appendix A for detailed descriptions of the Middle Cambrian through Pennsylvanian section in this area.

Overlying the Chilhowee Group is the Shady Dolomite. The boundaries of the Shady Dolomite in the Cartersville area are subject to some disagreement (Table 1). Kesler (1950) and Reade and others (1980) believe that the Shady Dolomite should be restricted to a basal, thin, black or dark-gray, fine-grained dolostone having paper-thin shale lamellae. In their interpretation, Reade and others (1980) place the overlying gray dolostone and interlayered dolostone and shale in the Rome Formation. In contrast, Cressler and others (1979) place all of the dolostones above the Chilhowee and below the Rome shales in the Shady Dolomite. Archaeocyathids were found in both the lower dark-gray unit and upper light-gray unit (Stan Sharden, personal commun., October, 1982). Costello and others (1982) note that the light-gray dolostones interfinger with shales that generally are assigned to the Rome Formation and indicate that they are time equivalents of the Rome Formation. This report follows the definition of the Shady Dolomite as reported by Cressler and others (1979) (Table 1).

The Rome Formation is composed of fine-grained, slightly calcareous, green to red sandstone (Butts and Gildersleeve, 1948). Sandstone is interlayered with greenish shale that weathers to a gray, pinkish or yellowish shale. Thin layers of limestone also are present.

Stratigraphy of the Blue Ridge

The Blue Ridge portion of the Greater Atlanta Regional Map is dominated by two major structural features which lie adjacent to each other (Fig. 3), the Salem Church anticlinorium and Murphy synclinorium. The determination of a stratigraphic succession in these two structures is complicated by 1) lack of continuous exposures, 2) multiple fold events, 3) both brittle and ductile faulting, 4) sedimentary facies changes, and 5) internal unconformities. The combination of the five above-mentioned factors has resulted in numerous, often conflicting, interpretations regarding the stratigraphic sequence. Generally, interpretations of the stratigraphic sequence in this area were dependent on whether or not the Corbin Gneiss Complex was considered as intrusive into the Blue Ridge sequence and if the Cartersville fault was interpreted to be present east of Cartersville. A brief summary of the various interpretations was presented in the Previous Works section of this report and will not be repeated here, but investigations related to this report (McConnell and Costello, 1980b, 1982a) have shown that Hayes' original work in the area, with minor modifications, is correct. Hayes' observations regarding the presence of a nonconformity between the




Figure 3. Major structural features of the Greater Atlanta Regional Map.

Stratigraphy of the Piedmont

NORTHERN PIEDMONT

Rocks lying between the Allatoona fault and the Brevard fault zone (Fig. 2) are defined in this report to be in the northern Piedmont. This usage diverges from common terminology used in Alabama, South Carolina and Georgia (i.e., Tull, 1978; Hurst, 1973; Hatcher, 1978a). In several recent reports (McConnell and Costello, 1980b; Abrams and McConnell, 1981a; McConnell and Abrams, 1982a, 1982b) the regional stratigraphy and structure in the northern Piedmont has been revised. These reports resulted from detailed and reconnaissance mapping carried out as part of the Greater Atlanta Regional Map project. A conclusion reached as a result of this mapping effort was that some names previously used to describe major rock units are no longer suitable. Prior to the studies mentioned above, major rock units in western Georgia were either assigned a numerical classification (Crawford and Medlin, 1973) or correlated with the Ashland and Wedowee units in Alabama (Hurst, 1973). The numerical classification used by Crawford and Medlin (1973) is inappropriate due to its dependence on a single major fold event as its basis. Multiple deformation and its influence on the local stratigraphy in the northern Piedmont is documented in many recent reports (Hatcher, 1977, 1978a; McConnell and Costello, 1980b; Abrams and McConnell, 1981a). The numerical designation therefore is abandoned in this report. Relating rocks of the northern Piedmont with the terms Ashland and Wedowee also is not appropriate. Ashland Mica Schist and Wedowee Formation are somewhat ambiguous field terms used by Prouty (1923) and Adams (1926) to describe major rock units in Alabama. Since its introduction, the name Ashland has held several different stratigraphic ranks including group status (Hurst, 1973) and supergroup status (Tull, 1978). Neathery and Reynolds (1973) suggested that the term "Ashland Mica Schist" be abandoned because they believe that units of the Wedowee Formation are traceable across metamorphic boundaries into rocks that were previously assigned to the Ashland Mica Schist. Also, the Wedowee Formation as defined by Bentley and Neathery (1970) contains units defined as part of the Ashland Supergroup by Tull (1978). To add to the confusion, rocks of the Ashland Supergroup as defined by Tull (1978) are present only in the Coosa block and rocks of the Wedowee are present only in the Tallapoosa block. Thomas and others (1979) indicate that only Tallapoosa block rocks (i.e., Wedowee Group and Emucklaw-Heard sequence) are present in west Georgia north of the Brevard fault zone. However, Hurst (1973) has defined rocks of both Wedowee Formation and Ashland Group in the northern Piedmont of Georgia.

Due to their ambiguous original definition, their subsequent accumulation of several different stratigraphic ranks, and confusion over their boundaries, McConnell and Costello (1980b) suggested that both Ashland and Wedowee be dropped as stratigraphic names in Georgia. To replace Ashland and Wedowee in Georgia, McConnell and Costello (1980b) informally introduced the names Dallas group and Roosterville group. These two groups together with the Sandy Springs Group (Higgins and McConnell, 1978a, 1978b) encompassed all major rock units in the northern Piedmont of Georgia. In a

subsequent report, Abrams and McConnell (1981a) revise the boundary between the Dallas and Roosterville groups and changed the name of the Dallas group to New Georgia Group (Fig. 11). As a result of the boundary change, sequences of rocks of dominantly volcanic origin comprise the New Georgia Group.

Although areal separation and apparent lithologic differences prohibit any direct correlation with rocks in Georgia, we speculate that rocks of the New Georgia Group are, at least in part, equivalent to rocks of the Ashland Supergroup (Table 4). This is based primarily on the fact that both the New Georgia Group and Ashland Supergroup contain a large proportion of metavolcanic rocks and similar types of deposits. In addition, we also suggest that rocks defined as Wedowee Formation in Alabama (Tull, 1978) are equivalent to rocks of the Sandy Springs Group, particularly rocks of the Sandy Springs Group western belt. This correlation is based on lithologic similarities and the association of both Sandy Springs Group and Wedowee Formation with major volcanic bearing rock groups (i.e., New Georgia Group and Ashland Supergroup, respectively).

In their preliminary report, McConnell and Costello (1980b) indicated that the Sandy Springs Group was the oldest rock sequence in the northern Piedmont. This interpretation was based on lithologic similarities between the Sandy Springs Group and Tallulah Falls Formation (Hatcher, 1974), the latter of which lies, at least in part, nonconformably on Grenville basement in northeast Georgia (Hatcher, 1977, 1978a). Hatcher (1978a) also speculated, however, that a large part of the Tallulah Falls Formation was deposited on oceanic crust. Recent mapping in western Georgia supports the oceanic crust hypothesis. Rocks of the New Georgia Group are interpreted to represent back-arc basin volcanics that formed on attenuated (rifted) continental crust. This interpretation is based on chemistry of the volcanic rocks in the New Georgia Group which is bimodal and suggests back-arc basin or ocean ridge tholeiite affinity (McConnell, 1980a; McConnell and Abrams, 1982b). The presence of attenuated and, possibly, largely engulfed continental crust is postulated to provide a source for the large volume of felsic volcanic rocks in the New Georgia Group and to provide a mechanism for the presence of Grenville basement unconformably beneath the Tallulah Falls Formation. We further speculate that as volcanic activity decreased in the basin, it was infilled by flysch facies greywackes, argillites and subordinate volcanic rocks of the Sandy Springs Group.

Another result of the detailed mapping in western Georgia is the confirmation of lithostratigraphic equivalence between rocks of the Roosterville group and Sandy Springs Group. McConnell and Costello (1980b) suggested the possible equivalence of the two units in their report. In this bulletin, we propose that the term "Roosterville group" be dropped and rocks previously within the Roosterville be considered to be the western belt of the Sandy Springs Group (Fig. 11). This proposal is based on lithologic similarities between units of the Sandy Springs Group and Roosterville group as well as on the presence of similar stratigraphic sequences in both groups.

In the following discussion an interpretation of the stratigraphic sequence in the northern Piedmont is presented. Due to a lack of definitive isotopic ages, regionally significant




Figure 11. Group and formation boundaries of the crystalline rocks of the Greater Atlanta Regional Map.

Paleozoic intrusive rocks in the Piedmont may be divided into three main categories. These general categories include plutons interpreted as 1) premetamorphic, 2) pre- to synmetamorphic, and 3) postmetamorphic. Timing of the Paleozoic metamorphic event in the Piedmont is not exactly defined, but was interpreted to have occurred in the Piedmont southeast of the Brevard fault zone 365 m.y. ago by Dallmeyer (1975). Abrams and McConnell (1981b) suggested that the age of peak metamorphism in the northern Piedmont also is approximately 365 m.y. ago. An upper limit on the timing of metamorphism in Georgia may be assumed to be 350 m.y. based on the age of Elberton Granite (Whitney and Wenner, 1980). The three main categories of plutons have distinct chemical signatures. These signatures characterize the evolutionary changes which this portion of the Appalachian orogen has undergone.

Premetamorphic Intrusives (Category 1)

Intrusive rocks in the Piedmont portion of the Greater Atlanta Regional Map that were emplaced prior to major metamorphic and deformational events often have their original character masked by these subsequent events. In particular, it is difficult to distinguish between a fine-grained metaplutonic rock and a metavolcanic rock due to obliteration of most igneous textures by subsequent recrystallization. However, several premetamorphic plutons are recognizable in this area. Most of the plutons of this category are in close proximity to extrusive rocks of similar composition. Because of this association we have termed these intrusive and extrusive rocks, intrusive-extrusive complexes. Other characteristics of plutons in this category are general concordance with regional trends, low potassium concentrations in felsic units and moderately high TiO_2 concentrations in mafic units.

In the northern Piedmont, intrusive-extrusive complexes are recognized only in the New Georgia Group where they are associated with numerous volcanogenic massive sulfide and gold deposits (Abrams and others, 1981; McConnell and Abrams, 1982b). Intrusions of this category also have been affected by all major episodes of penetrative deformation to have affected the Piedmont. The Villa Rica Gneiss, Laura Lake Mafic Complex, Acworth Gneiss, Kellogg Creek Mafic Complex and Galts Ferry Gneiss are members of the premetamorphic category north of the Brevard fault zone, while biotite-plagioclase gneisses in the Big Cotton Indian, Camp Creek, and possibly Promised Land Formations as well as the Norcross Gneiss may represent premetamorphic intrusive-extrusive complexes south of the Brevard zone.

One of the characteristics of premetamorphic felsic to intermediate intrusive rocks in the New Georgia Group is the low concentration of potassium in these rocks. This characteristic is documented by major element analyses of the Galts Ferry Gneiss, Villa Rica Gneiss and Dallas gneiss (Table 5; Fig. 30) and modal analyses of the Villa Rica, Dallas, Galts Ferry and Acworth Gneisses (Table 9; Fig. 14). At this stage, some consideration must be given to the fact that potassium, due to its high mobility during metamorphism, may have migrated out of the felsic gneisses of this category (James Tull, personal commun., 1983). However, we find no evidence for this migration and feel that it would be fortuitous for potassium migration to occur preferentially in one rock unit in the northern Piedmont (New Georgia Group) with respect to another (Austell Gneiss). While we believe that potassium,

sodium, aluminum, and magnesium alteration has affected many of the rocks in the New Georgia Group as seen in the coarse garnet-chlorite schists and coarse kyanite-quartz granofels, we interpret these as primary features formed largely by the hydrothermal plumbing system present when volcanic rocks of the New Georgia Group were being deposited.

Mafic intrusive complexes of category 1 in the northern Piedmont are the Laura Lake and Kellogg Creek Mafic Complexes. The Laura Lake and Kellogg Creek Complexes are apparently associated with mafic extrusives and with rocks of dacitic composition (i.e., Acworth Gneiss in association with the Kellogg Creek, see Plate I; and felsic components in the Laura Lake Complex).

The Laura Lake Mafic Complex is the largest intrusive-extrusive complex (approximately 80 sq. mi.) in the Piedmont portion of the Greater Atlanta Regional Map (Plate I). The term Laura Lake Mafic Complex was introduced informally by McConnell and Costello (1980b) to describe a large body of amphibolite, metagabbro and meta-ultramafic rocks in eastern Cobb and southern Cherokee Counties (Plate I). We propose to elevate the term to formal status. The Laura Lake Mafic Complex is named for exposures near Laura Lake in eastern Cobb County (Fig. 31).

The areal extent and mafic character of the Laura Lake Mafic Complex should result in a significant aeromagnetic signature; however, aeromagnetic maps currently available characterize the Laura Lake Complex as a series of elongate highs and lows (Higgins and Zietz, 1975). The composite mass of Laura Lake Complex is not distinguishable on aeromagnetic maps. This contrasts with iron formations associated with the Pumpkinvine Creek and Lost Mountain Formations (Higgins and Zietz, 1975) that form linear aeromagnetic highs in western Cobb County. Very high magnetic anomalies noted as Kennesaw Mountain by Higgins and Zietz (1975) probably are either an expression of iron formation known to be near this area or magnetite porphyroblasts present in the amphibolite and leucocratic gneiss (Fig. 32). Although Higgins and Zietz (1975) suggested that the gneiss at Kennesaw Mountain was allochthonous, lack of a significant aeromagnetic signature for the entire Laura Lake suggests that the complex is thin and probably rootless.

Chemically, the Laura Lake Complex bears some similarity to amphibolites in the New Georgia Group. The Laura Lake is separated from the outcrop belt of the New Georgia Group by a thin strip of Sandy Springs Group rocks. The outcrop pattern of the Laura Lake Complex suggests that it crosscuts stratigraphy in the Sandy Springs Group, particularly in central Cobb County where the Laura Lake Complex lies structurally beneath the Chattahoochee Palisades Quartzite at Sweat and Blackjack Mountains (Plate I). The aforementioned relationships suggest that the Laura Lake may have intruded rocks of the Sandy Springs Group. Due to lithologic similarities between the New Georgia Group and Laura Lake Complex, an alternative interpretation, which is favored by this report, is that the Laura Lake represents a slice of the New Georgia Group that, along with the Sandy Springs Group, was thrust over units of the New Georgia Group along the Chattahoochee fault (Plate I). Local faulting along the eastern margin of the Laura Lake Complex cuts out portions of the Sandy Springs Group. Rock exposures and (or) mapping are not extensive enough to conclusively prove one interpretation over another.




Figure 30. Plot of normative analyses of felsic igneous rocks in the Greater Atlanta Regional Map area, classification modified after Streckeisen (1976) modal diagram with quartz monzonite field added. Analyses after Grant and others (1980); Abrams (1983); this report. 1=Quartz-rich granitoids, 2=Alkali-feldspar granite, 3=Two-feldspar granite, 4=Quartz monzonite, 5=Granodiorite, 6=Quartz diorite, 7=Alkali-feldspar-quartz syenite, 8=Quartz syenite, 9=Quartz-rich monzonite, 10=Quartz monzodiorite, 11=Tonalite, 12=Alkali-feldspar syenite, 13=Syenite, 14=Monzonite, 15=Monzodiorite, 16=Diorite.




Figure 31. Type locality of the Laura Lake Mafic Complex (U.S. Geological Survey, Kennesaw, Georgia, 1:24,000 topographic quadrangle).



Figure 32. Photograph of magnetite porphyroblasts in exposure of the Laura Lake Mafic Complex, Interstate 575 at Bells Ferry Road exit.

The Laura Lake Mafic Complex is composed predominantly of migmatitic garnet amphibolite with smaller amounts of clinopyroxene (relict, altering to amphibole)-bearing metagabbro, felsic gneiss, meta-ultramafic lithologies and banded iron formation. Magnetite occurs as medium to coarse grains in felsic members and in grains as large as ¼ in. across as common porphyroblasts in amphibolite. Leucocratic neosome in the Laura Lake is composed of very coarse-grained amphibole-quartz-plagioclase (An₃₂) rock. Amphiboles in the neosome were observed to reach 1½ in. across (Fig. 33). A distinct and mappable unit of intermediate gneiss is present along the western margin of the Laura Lake Mafic Complex (Plate I). This gneiss is locally quarried for aggregate near Kennesaw and has a quartz diorite composition (Sample 6, Table 12). Hurst (1962) informally termed this rock Kennesaw gneiss. This report proposes to formally designate the Kennesaw Gneiss Member of the Laura Lake Mafic Complex for exposures east of the town of Kennesaw (Fig. 34).

Another premetamorphic mafic complex is present west of the outcrop area of the Laura Lake Complex, in the New Georgia Group in southern Bartow, northeastern Paulding and northwestern Cobb Counties (Plate I). McConnell and Costello (1980b) informally termed this unit the Kellogg Creek metagabbro. Crawford and Medlin (1970) described this rock as being sheared and concordant with the regional trend. Like the Laura Lake Complex, the Kellogg Creek is composed of garnet amphibolite, metagabbro and lesser amounts of meta-ultramafic rocks. Although no direct evidence for an extrusive facies were observed, amphibolites associated with the metagabbro may possibly represent an extrusive component. The variety of rock types associated with the Kellogg Creek suggests that "gabbro" is not an appropriate term to describe this unit. In this report, therefore, the Kellogg Creek metagabbro is formally designated the Kellogg Creek Mafic Complex for exposures along Kellogg Creek in southern



Figure 33. Photograph of coarse amphiboles in the Laura Lake Mafic Complex, Interstate 575 just east of Interstate 75.

Cherokee County (Fig. 35). Chemically, rocks of the Kellogg Creek Complex are distinct from either the Laura Lake Mafic Complex or other amphibolites in the New Georgia Group (Table 12, samples labeled KC; Fig. 36). The gabbroic facies of the Kellogg Creek generally is higher in aluminum and lower in TiO₂ than other mafic rocks in this area (Fig. 36). While it may have an associated extrusive facies, the Kellogg Creek Complex may not be related to documented mafic volcanic rocks in the New Georgia Group.





Figure 34. Type locality of the Kennesaw Gneiss Member of the Laura Lake Mafic Complex (U.S. Geological Survey, Kennesaw, Georgia, 1:24,000 topographic quadrangle).



Reference No. 4

GROUND WATER IN THE GREATER ATLANTA REGION, GEORGIA

by
**C. W. Cressler, C. J. Thurmond,
and W. G. Heister**

Prepared in cooperation with the
U. S. Geological Survey
Department of Natural Resources
Environmental Protection Division
Georgia Geologic Survey

INFORMATION CIRCULAR 63

In table 7, which lists chemical analyses of well water, some wells retain numbers used in previous reports.

WATER-BEARING UNITS AND THEIR HYDROLOGIC PROPERTIES

The part of the GAR included in this study lies wholly within the Piedmont physiographic province (Clark and Zisa, 1976; Fenneman, 1938). The area is underlain by a complex of metamorphic and igneous rocks that have been divided by various workers into more than 50 named formations and unnamed mappable units. Individual rock units range in thickness from less than 10 ft to possibly more than 10,000 ft.

Regional stresses have warped the rocks into complex folds and refolded folds, and the sequence has been injected by igneous plutons and dikes and broken by faults. Erosion of these folded and faulted rocks produced the complex outcrop patterns that exist today. The large number of rock types in the area

and their varied outcrop patterns greatly complicate the occurrence and availability of ground water in the area. Nevertheless, many of the more than 50 named formations and unnamed mappable units in the GAR are made up of rocks that have similar physical properties and yield water of comparable quantity and chemical quality. Thus, for convenience, the rocks in the report area have been grouped into nine principal water-bearing units and assigned letter designations. The areal distribution of the water-bearing units and their lithologies are shown on plate 1. Data on wells in the water-bearing units are summarized in tables 1-3.

OCCURRENCE AND AVAILABILITY OF GROUND WATER

Ground water in the GAR occupies joints, fractures, and other secondary openings in bedrock and pore spaces in the overlying mantle of residual material. Water recharges the underground

Table 1.—Summary of well data for the Greater Atlanta Region

Water-bearing unit	Number of wells	Yield (gal/min)		Depth (ft)		Casing depth (ft)		Topography (percent of wells in each setting)						
		Range	Average	Range	Average	Range	Average	Slope	Broad lowlands	Upland-ridge crests	Draw, hollow	Stream or lake	Saddle	Other
A Amphibolite-gneiss-schist	363	20-275	56	35-2,175	294	0-200	60	22	35	22	4	11	2	4
B Granitic gneiss	166	20-348	72	40-825	271	3-264	54	33	45	2	14	6	0	0
C Schist	100	20-150	47	67-700	195	6-144	53	19	19	27	20	11	4	0
D Metite gneiss	78	20-351	56	83-710	270	7-140	56	20	27	36	6	11	0	0
E Mafic	32	20-471	79	67-384	191	8-116	46	17	35	28	3	17	0	0
F Granite	43	20-150	43	43-422	192	11-187	57	30	30	15	15	10	0	0
G Cataclastic	55	20-225	74	110-800	323	8-207	84	4	75	15	4	2	0	0
H Quartzite	12	20-200	72	122-500	297	30-85	58	45	9	27	18	0	0	0
J Carbonate	5	31-150	76	240-505	376	28-314	138	0	100	0	0	0	0	0

openings by seeping through this material or by flowing directly into openings in exposed rock. This recharge is from precipitation that falls in the area.

Unweathered and unfractured bedrock in the report area has very low porosity and permeability. Thus, the quantity of water that a rock unit can store is determined by the capacity and distribution of joints, fractures, and other types of secondary openings. The quantity of stored water that can be withdrawn by wells depends largely on the extent to which the rock openings are interconnected.

The size, spacing, and interconnection of openings differ greatly from one type of rock to another and with depth below land surface. Open joints and fractures tend to become tighter and more widely spaced with increasing depth. Joints and other openings in soft rocks such as phyllite tend to be tight and poorly connected; wells in rocks of this character generally have small yields. On the other hand, openings in more brittle rocks such as quartzite and graywacke tend to be larger and are better connected; wells in these rocks normally supply greater yields. Other rocks, including amphibolite, schist, and gneiss, are variable in the size and connection of secondary openings and generally yield small to moderate quantities of water to wells. Carbonate rocks, which include marble, can contain much larger and more extensively interconnected fracture systems. Openings in carbonate rocks commonly are enlarged by solution, and are capable of transmitting large quantities of water.

Effects of Drainage Style

The GAR is divided nearly in half by the Chattahoochee River, which follows a comparatively straight southwesterly course for nearly 110 miles across the area (fig. 1). Streams in the north half of the area, including the Chattahoochee River and its tributaries, mainly have

rectangular and trellis drainage styles. In contrast, streams in the south half of the area, beginning at about the south edge of the Chattahoochee River basin, have a dendritic drainage style (Staheli, 1976).

Streams having rectangular drainage style flow in strongly angular courses that follow the rectangular pattern of the joints that break up the rocks. Areas having trellis drainage style are characterized by strongly folded and dipping rocks; the larger streams follow the outcrops of less resistant rocks and tributaries enter at right angles across the dip of the strata (Lobeck, 1939, p. 175). All of the streams in the north half of the area show the influence of geologic control, their drainage styles reflecting the varied outcrop pattern, the different lithologies present, and the geologic structure.

In the south half of the area, the dendritic drainage style is indicative of streams that developed independently of the underlying geology (LaForge and others, 1925; Staheli, 1976). According to Staheli (1976, p. 451), dendritic drainage, in which streams run in all directions like the branches of a tree, probably was established on some pre-existing surface and later superimposed on the underlying crystalline rocks. Such streams are said to be superimposed when they acquire a course on nearly flat-lying material that covered the rocks beneath. Streams flowing on the veneer of material that covers the bedrock are superimposed above the concealed rocks. When rejuvenated by uplift, they become incised and develop courses without regard to the structure or lithology of the underlying rocks. Eventually, the cover material may be entirely removed and then only the physiographic pattern of the streams will suggest their having been let down from a superimposed position (Lobeck, 1939, p. 173).

According to Staheli (1976, p. 451), to explain the different drainage styles in regions underlain by similar rocks and

Table 9.—Record of wells in the Greater Atlanta Region—Continued

Well No.	Owner	Water-bearing unit	Latitude and Longitude	Yield (gal/min)	Depth (ft)	Casing		Date drilled	Driller	Elevation (ft)	Water level below land surface	
						depth (ft)	diam. (in.)				Static head (ft)	Pumping head (ft)
Cobb County												
8GG2	Johnny R. Davidson 6216 Cedar Crest Rd. Acworth	D	34°03'35" 84°43'54"	100	185	141	6	7/72	Virginia	900	--	--
8GG3	Fairway Mobile Home Park 4715 Cobb Pkwy, N. Acworth	D	34°34'00" 84°43'34"	110	374	63	6	1973	Ward	910	--	--
8GG5	W. L. Singletary Ellie Rd. Kennesaw	A	34°00'47" 84°38'12"	30	106	52	6	1970	do.	1,120	--	--
8GG6	City of Acworth Seminole Dr. Acworth	D	34°03'44" 84°40'45"	60	500	70	8	--	Virginia	870	--	--
8GG7	do.	D	34°03'55" 84°40'45"	49	500	--	8	--	do.	900	33	134
9EE2	John R. Boggs 571 Boggs Rd. Mableton	C	33°48'13" 84°34'15"	32	222	89	6	6/63	do.	1,025	15	209
9FF1	City of Smyrna Spring St. Smyrna	C	33°52'59" 84°30'40"	110	131	--	8	Before 1949	do.	1,045	--	--
9FF2	Cobb County Airport Dobbins AFB Marietta	C	33°54'55" 84°30'06"	75	235	80	8	Before 1949	do.	1,000	--	--
9FF3	Lockheed Co. Marietta	C	33°55'11" 84°30'49"	72	131	44	--	1951	do.	980	--	--
9FF4	do.	C	33°55'20" 84°31'01"	68	513	21	--	1951	do.	980	--	--
9FF5	do.	C	33°55'23" 84°31'14"	73	550	49	--	1951	do.	1,010	--	--
9FF6	Town & County Investmt. Co. 1106 Mossey Rock Rd., NW Kennesaw	A	33°58'51" 84°35'53"	43	155	42	6	1977	Ward	930	--	--
9FF7	David S. Field 1389 Bella Ferry Rd. Marietta	C	33°59'06" 84°33'31"	30	180	40	6	1976	do.	1,170	--	--
9GG1	Charles Hutson Rte. 6, Ebenezer Rd. Marietta	A	34°02'03" 84°30'09"	35	104	22	6	1969	do.	1,065	--	--
10FF1	Richard Ardell 15601 Old Canton Rd., NE Marietta	C	33°59'18" 84°27'54"	35	205	54	6	5/74	Virginia	1,000	--	--
10FF2	Riverbend Apts. 6640 Akers Mill Rd., NW Atlanta	C, H	33°53'48" 84°26'42"	42	95	70	6	12/67	do.	780	16	84

Reference No. 5

CLIMATIC ATLAS OF THE UNITED STATES



U.S. DEPARTMENT OF COMMERCE

C. R. Smith, Secretary

ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION

Robert M. White, Administrator

ENVIRONMENTAL DATA SERVICE

Woodrow C. Jacobs, Director


JUNE 1968

REPRINTED BY THE


NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION

1983

NORMAL ANNUAL TOTAL PRECIPITATION (Inches)



**MEAN ANNUAL LAKE EVAPORATION
(In Inches)**



NUS CORPORATION AND SUBSIDIARIES**TELECON NOTE**

Reference No. 7

CONTROL NO.**DATE:** February 9, 1989**TIME:** 0920**DISTRIBUTION:**

File Cobb County, Georgia

BETWEEN: Jim Smith, Design**OF:** Cobb County Water System**PHONE:** (404) 423-1000**AND:** Geoffrey Carton**DISCUSSION:**

Mr. Smith reported that 99% of the residences in Cobb County are supplied by municipal water. The Cobb-Marietta water authority sells water to municipal systems in the county. Their water sources are Lake Alltoona and the Chattahoochee River at Johnson Ferry Road. Both Marietta and Smyrna have their own water systems. *AC*

Reference No. 8

Water Availability & Use

CHATTAHOOCHEE RIVER BASIN

**Georgia Department of Natural Resources
Environmental Protection Division**

WATER AVAILABILITY AND USE

CHATTAHOOCHEE RIVER BASIN

GEORGIA

1984

NUS CORPORATION AND SUBSIDIARIES**TELECON NOTE**

Reference No. 9

CONTROL NO.**DATE:** February 8, 1989**TIME:** 1420**DISTRIBUTION:**

File
Cobb County, Georgia
DeKalb County, Georgia

BETWEEN: Kris Martin**OF:** GA Dept. of Natural Resources**PHONE:** (404) 656-4817**AND:** Geoffrey Carton, NUS Corporation**DISCUSSION:**

All streams in both counties have fish life. There is recreational fishing on most streams in both DeKalb and Cobb counties. The exceptions would be the small headwaters. There is commercial fishing on major reservoirs and rivers (i.e. South River and Yellow River). There is no commercial fishing on the Chattahoochee River as it is designated a secondary trout stream. *JK*

ACTION ITEMS:

ENDANGERED AND THREATENED SPECIES



U.S. FISH AND WILDLIFE SERVICE
REGION 4 - ATLANTA

HAZARD RANKING SYSTEM SCORING SUMMARY

FOR

AMERICAN METALS COMPANY, INC.
EPA SITE NUMBER 6AD000827973
MARIETTA
COBB COUNTY, GA
EPA REGION: 4

SCORE STATUS: IN PREPARATION

SCORED BY GEOFFREY CARTON
OF NUS CORPORATION
ON 04/03/89

DATE OF THIS REPORT: 05/26/89
DATE OF LAST MODIFICATION: 05/26/89

GROUND WATER ROUTE SCORE :	9.52
SURFACE WATER ROUTE SCORE:	7.27
AIR ROUTE SCORE :	0.00

MIGRATION SCORE :	6.92

HRS GROUND WATER ROUTE SCORE

CATEGORY/FACTOR	RAW DATA	ASN. VALUE	SCORE
1. OBSERVED RELEASE	NO	0	0
2. ROUTE CHARACTERISTICS			
DEPTH TO WATER TABLE	180 FEET		
DEPTH TO BOTTOM OF WASTE	5 FEET		
DEPTH TO AQLIFR OF CONCERN	174 FEET	0	0
PRECIPITATION	48.0 INCHES		
EVAPORATION	41.0 INCHES		
NET PRECIPITATION	7.0 INCHES	2	2
PERMEABILITY	1.0×10^{-4} CM/SEC	2	2
PHYSICAL STATE		3	3
TOTAL ROUTE CHARACTERISTICS SCORE:			7
3. CONTAINMENT		3	3
4. WASTE CHARACTERISTICS			
TOXICITY/PERSISTENCE: CHROMIUM			10
WASTE QUANTITY	CUBIC YDS	2501	
	DRUMS	0	
	GALLONS	0	
	TONS	0	
TOTAL	2501 CU. YDS	8	8
TOTAL WASTE CHARACTERISTICS SCORE:			21
5. TARGETS			
GROUND WATER USE		2	2
DISTANCE TO NEAREST WELL AND	12000 FEET		
TOTAL POPULATION SERVED	MATRIX VALUE	4	4
NUMBER OF HOUSES	4 PERSONS		
NUMBER OF PERSONS	1		
NUMBER OF CONNECTIONS	0		
NUMBER OF IRRIGATED ACRES	0		
TOTAL TARGETS SCORE:			6
GROUND WATER ROUTE SCORE (Sgw) = 9.32			

HRS SURFACE WATER ROUTE SCORE

CATEGORY/FACTOR		RAW DATA	ASN. VALUE	SCORE
1. OBSERVED RELEASE		NO	0	0
2. ROUTE CHARACTERISTICS				
SITE LOCATED IN SURFACE WATER		NO		
SITE WITHIN CLOSED BASIN		NO		
FACILITY SLOPE		2.0 %		
INTERVENING SLOPE		2.0 %	0	0
24-HOUR RAINFALL		4.0 INCHES	2	3
DISTANCE TO DOWN-SLOPE WATER		2300 FEET	2	4
PHYSICAL STATE		3		3
TOTAL ROUTE CHARACTERISTICS SCORE:				10
3. CONTAINMENT		3		3
4. WASTE CHARACTERISTICS				
TOXICITY/PERSISTENCE: CHROMIUM				18
WASTE QUANTITY	CUBIC YDS	2501		
	DRUMS	0		
	GALLONS	0		
	TONS	0		
	TOTAL	2501 CU. YDS	2	3
TOTAL WASTE CHARACTERISTICS SCORE:				21
5. TARGETS				
SURFACE WATER USE			2	0
DISTANCE TO SENSITIVE ENVIRONMENTS			0	0
COASTLINE		NONE		
FRESH WATER WETLANDS		NONE		
CRITICAL HABITAT		NONE		
DISTANCE TO STATIC WATER		> 3 MILES		
DISTANCE TO WATER SUPPLY INTAKE		> 3 MILES		
AND		MATRIX VALUE	0	0
TOTAL POPULATION SERVED		0		
NUMBER OF HOUSES		0		
NUMBER OF PERSONS		0		
NUMBER OF CONNECTIONS		0		
NUMBER OF IRRIGATED ACRES		0		
TOTAL TARGETS SCORE:				0
SURFACE WATER ROUTE SCORE (SEW) =				0.27

HRS AIR ROUTE SCORE

<u>CATEGORY/FACTOR</u>	<u>RAW DATA</u>	<u>ASN. VALUE</u>	<u>SCORE</u>
1. OBSERVED RELEASE	NO	0	0
2. WASTE CHARACTERISTICS			
PERMEABILITY			
INCOMPATIBILITY		MATRIX VALUE	
TOXICITY			
WASTE QUANTITY	CUBIC YARDS		
	DRUMS		
	GALLONS		
	TONS		
	TOTAL		
TOTAL WASTE CHARACTERISTICS SCORE:			N/A

3. TARGETS

POPULATION WITHIN 4-MILE RADIUS

0 to 0.25 mile

0 to 0.50 mile

0 to 1.0 mile

0 to 4.0 miles

DISTANCE TO SENSITIVE ENVIRONMENTS

COASTAL WETLANDS

FRESH-WATER WETLANDS

CRITICAL HABITAT

DISTANCE TO LAND USES

COMMERCIAL/INDUSTRIAL

PARK/FOREST/RESIDENTIAL

AGRICULTURAL LAND

PRIME FARMLAND

HISTORIC SITE WITHIN VIEW?

TOTAL TARGETS SCORE:

N/A

AIR ROUTE SCORE (Sa) = 0.00

HAZARD RANKING SYSTEM SCORING CALCULATIONS
FOR
SITE: AMERICAN METALS COMPANY, INC.
AS OF 05/26/89

PAGE 3

GROUND WATER ROUTE SCORE

ROUTE CHARACTERISTICS		7
CONTAINMENT	X	3
WASTE CHARACTERISTICS	X	25
TARGETS	X	10

$$= \frac{5460}{57,330} \times 100 = 9.52 = S_{gw}$$

SURFACE WATER ROUTE SCORE

ROUTE CHARACTERISTICS		10
CONTAINMENT	X	3
WASTE CHARACTERISTICS	X	26
TARGETS	X	6

$$= \frac{4680}{64,350} \times 100 = 7.27 = S_{sw}$$

AIR ROUTE SCORE

$$\text{OBSERVED RELEASE} \quad 0 / 35,100 \times 100 = 0.00 = S_{air}$$

SUMMARY OF MIGRATION SCORE CALCULATIONS

	<u>S</u>	<u>S²</u>
GROUND WATER ROUTE SCORE (S _{gw})	9.52	90.63
SURFACE WATER ROUTE SCORE (S _{sw})	7.27	52.85
AIR ROUTE SCORE (S _{air})	0.00	0.00
$S^2_{gw} + S^2_{sw} + S^2_{air}$		143.48
$\sqrt{(S^2_{gw} + S^2_{sw} + S^2_{air})}$		11.98
$S_M = \sqrt{(S^2_{gw} + S^2_{sw} + S^2_{air})} / 1.73$		6.9

Reference
#6

OVERSIZED

DOCUMENT

MAP

entered
850627
C/B Warren

PRELIMINARY ASSESSMENT COVER SHEET
AMERICAN METALS COMPANY INC.
GAD000827873

Operations at this facility began in 1969 under the ownership of Southcoats. In 1975, the plant was sold to Prior Coated Metals, Inc. who operated the facility until it was purchased by the American Metals Co., Inc. in 1980. Since its inception in 1969, the facility has been used to paint rolls of steel sheeting. This facility is presently classified as a generator; its Part A application has been withdrawn.

In a phone conversation on 6/17/85, the facility engineer, Mr. Carl Houser, seemed unsure of hazardous waste handling practices prior to 1980. Since that date, the facility has generated small quantities of waste paint, solvents, caustics and chromic acids. These wastes have been discharged under permit to the local POTW. A wastewater treatment system was operative at one time during the 1970's or early 1980's. The system was apparently cleaned out and the accumulated sludges were drummed. In a conversation on 6/17/85, Frances Hallahan of the Georgia EPD stated that when she visited the site on 1/16/85, several rusty drums containing waste water treatment sludges were located in back of the facility. Ms. Hallahan indicated that the Generator Compliance Unit of the Georgia EPD is requiring the facility to furnish analytical results for the sludge. The facility plans to have a new waste water treatment system in operation by December 1985.

The facility is located in an industrial park adjacent to Marietta, Georgia. The area around the facility is moderately to heavily populated. Surface run-off from the site enters a small lake about 1/4 mile to the south. Ground water is not known to be used in the site area.

The site is assessed a "~~low~~" priority for a Site Inspection because information on hazardous waste handling practices prior to 1980 is incomplete.

MEDIUM

CSW/mcw020



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
GA 0000827873

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) American Metals Company, Inc.		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 1150 Marietta Industrial Drive, NE			
03 CITY Marietta	04 STATE GA	05 ZIP CODE 30062	06 COUNTY Cobb	07 COUNTY CODE 067	08 CONG DIST 07
09 COORDINATES: LATITUDE 33° 58' 43.5"		LONGITUDE 084° 32' 16.0"			
10 DIRECTIONS TO SITE (Starting from nearest public road) From Intersection of Hwy. 41 and Allgood Road, proceed north on Hwy 41 and turn right (NE) on 1 st road to the right. Proceed 1/4 mile to Web Drive and turn right (east). Proceed for 1,000 yds. and turn left (north) onto Marietta Industrial Drive. The facility is the last building on the right at the end of the road.					

III. RESPONSIBLE PARTIES

01 OWNER (if known) Donn Corporation		02 STREET (Business, mailing, residential) 1000 Crocker Road			
03 CITY West Lake	04 STATE OH	05 ZIP CODE 44145	06 TELEPHONE NUMBER '216' 871-1000		
07 OPERATOR (if known and different from owner)		08 STREET (Business, mailing, residential)			
09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER ()		
13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN					
14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply) <input checked="" type="checkbox"/> A. RCRA 3001 DATE RECEIVED: ____/____/____ MONTH DAY YEAR <input type="checkbox"/> B. UNCONTROLLED WASTE SITE (CERCLA 102(c)) DATE RECEIVED: ____/____/____ MONTH DAY YEAR <input type="checkbox"/> C. NONE					

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE 02.08.85 MONTH DAY YEAR <input type="checkbox"/> NO		BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input checked="" type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) F. Hallahan CONTRACTOR NAME(S): _____			
02 SITE STATUS (Check one) <input checked="" type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN		03 YEARS OF OPERATION BEGINNING YEAR 1969 ENDING YEAR continuing <input type="checkbox"/> UNKNOWN			
04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED caustics chromic acid paint sludges solvents (unspecified)					
05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION Low - information on hazardous waste handling prior to 1980 is incomplete.					

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents) <input type="checkbox"/> A. HIGH (inspection required promptly) <input checked="" type="checkbox"/> B. MEDIUM (inspection required) <input checked="" type="checkbox"/> C. LOW (inspect on time available basis) <input type="checkbox"/> D. NONE (No further action needed, complete current disposition form)	
---	--

VI. INFORMATION AVAILABLE FROM

01 CONTACT Carl Patton-Plant Supt.		02 OF (Agency, Organization) American Metals Company, Inc.		03 TELEPHONE NUMBER '404' 427-9471	
04 PERSON RESPONSIBLE FOR ASSESSMENT Steve Walker		05 AGENCY DNR	06 ORGANIZATION EPD-RAU	07 TELEPHONE NUMBER '404' 656-7404	08 DATE 06.17.85 MONTH DAY YEAR

J. Nowic



01 STATE	02 SITE NUMBER
----------	----------------

GA	D000827873
----	------------

01 PHYSICAL STATES (check all that apply)

☐ E SLURRY
☒ F LIQUID
☐ G GAS

D OTHER

02 WASTE QUANTITY AT SITE

Measures of waste quantities
 (kg of respondent)

TONS _____

YARDS

NO OF DRUMS unknown — —

03 WASTE CHARACTERISTICS (Check all that apply)

<input checked="" type="checkbox"/> A TOXIC	<input type="checkbox"/> E SOLUBLE
<input type="checkbox"/> B CORROSIVE	<input type="checkbox"/> F INFECTIOUS
<input type="checkbox"/> C RADIOACTIVE	<input checked="" type="checkbox"/> G FLAMMABLE
<input type="checkbox"/> D PERSISTENT	<input type="checkbox"/> H IGNITABLE

☐ E SOLUBLE
☐ F INFECTIOUS
☒ G FLAMMABLE
☐ H IGNITABLE

- ☐ I HIGHLY VOLATILE
- ☐ J EXPLOSIVE
- ☐ K REACTIVE
- ☐ L INCOMPATIBLE
- ☐ M NOT APPLICABLE

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE	unknown	----	containing paint wastes, solvents and caustics.
OLW	OILY WASTE			
SOL	SOLVENTS	unknown	----	unspecified chlorinated solvents
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS	unknown	----	chromic acid
BAS	BASES	unknown	----	in sludges
MES	HEAVY METALS	unknown	----	in paint wastes and chromic acid

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

[illegible]

V. FEEDSTOCKS See Appendix for C.A.S. Numbers

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

VI. SOURCES OF INFORMATION (Cite specific references, e.g., State files, sample analysis, reports.)

Trip Report by Frances Hallahan dated 2/8/85 and telephone conversation with the facility engineer on 6/17/85 - Memo attached.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

GA D000827873

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ B. SURFACE WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ C. CONTAMINATION OF AIR
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ E. DIRECT CONTACT
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☒ F. CONTAMINATION OF SOIL
03 AREA POTENTIALLY AFFECTED: 1 - 3
(Acres)

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☒ POTENTIAL ☐ ALLEGED

Hazardous waste handling practices prior to 1980 are unknown.

01 ☐ G. DRINKING WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ H. WORKER EXPOSURE/INJURY
03 WORKERS POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

01 ☐ I. POPULATION EXPOSURE/INJURY
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

GA D000827873

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES

(Seepage, small standing liquids, leaking drums)

03 POPULATION POTENTIALLY AFFECTED: unknown

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

Hazardous waste handling practices prior to 1980 are unknown.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: unknown


IV. COMMENTS

In a phone conversation on 6/17/85, Carl Houser (Facility Engineer) seemed uncertain of hazardous waste handling procedures at the site prior to 1980.

V. SOURCES OF INFORMATION (in specific references, e.g., state files, sample analysis reports)

Phone conversation on 6/17/85 with the Facility Engineer, Carl Houser -
Memo attached.

Figure 1; Site Location Map - American Metals Company, Inc.



PRELIMINARY ASSESSMENT
TELEPHONE CONVERSATION RECORD

Site Name: American Mfg. Company Inc. I.D.# CA0008078002

Location Address: 1150 Brown Ind Dr. Atlanta Ga.

Phone: (404) 427-9471.

Contact: Carl Hansen Title: Facility Engineer

Address: 1600 Crocker Rd. West Lake, Ga 30145

Phone: ¹⁻⁸⁰⁰ () 321-4199.

Authority: Section 3012 of CERCLA, Comprehensive Environmental Response, Compensation and Liability Act.

Facility has notified EPA via - RCRA 3001 site is in HWDMS -
CERCLA 103c site is in NOTIS

Need Information concerning waste generation and disposal prior to Nov. 19, 1980.

How long has facility been in operation? Since 1971

What kind of wastes were generated and how much?

chlorinated solvents, some waste paint, caustics and
small amounts of acid.

Was it disposed on site and where?

"not to my knowledge"

Was it transported offsite and where?

past - unknown, current - all hazardous waste is currently
discharged to the local sewer.

Was it treated and how?

past - unknown, current - discharged to POTW

Have there been any past spills? Describe.

"not to my knowledge"

Date of call: 6/17/85 Time: 1:55 p.m.

Tom Walker



JOE D. TANNER
Commissioner

Department of Natural Resources

ENVIRONMENTAL PROTECTION DIVISION
270 WASHINGTON STREET S.W.
ATLANTA, GEORGIA 30334

J. LEONARD LEDBETTER
Division Director

FILE COPY September 7, 1983

Mr. Sandor Frecska
Manager, Manufacturing Eng.
Donn Corporation
1000 Crocker Road
Westlake, OH 44145

RE: Request for Facility Status
Changes for American Metals Co.
Marietta, GA GAD000827873

Dear Mr. Frecska:

This will acknowledge receipt of your request for withdrawal of your application for a Hazardous Waste Facility permit.

Based on the information provided, and an inspection made on August 30, 1983, withdrawal of your application is warranted and your permit application has been placed in our inactive files.

As requested, your status has been changed to a generator and your EPA Identification Number has been retained. Storage of waste for less than ninety (90) days requires compliance with 40 CFR 262.34 of Georgia's Rules for Hazardous Waste Management.


Please be advised that withdrawal of your permit application invalidates any variance that you received to continue existing hazardous waste treatment storage or disposal during the permit review process and that based on our concurrence with your withdrawal request, the Federal Environmental Protection Agency will terminate your facility's interim status.

Should you wish to treat, store, or dispose of hazardous waste in the future, it will be necessary that a hazardous waste handling permit be issued, prior to the construction of such facilities, under authority of Section 8 of the Georgia Hazardous Waste Management Act and paragraphs .10 and .11 of Georgia's Rules for Hazardous Waste Management, Chapter 391-3-11.

Mr. Sandor Frecska
Donn Corp.
September 7, 1983
Page 2

If further clarification is needed on this matter, please feel free to contact Ms. Verona Barnes at 404/656-7802.

Sincerely,



John D. Taylor, Jr., Program Manager
Industrial & Hazardous Waste
Management Program

JDT:vbb:680

cc: James H. Scarbrough
Joe Surowiec
David Cheek
File: American Metals Co. (Y)



Department of Natural Resources

ENVIRONMENTAL PROTECTION DIVISION

270 WASHINGTON STREET S W

ATLANTA, GEORGIA 30334

TRIP REPORT

February 8, 1985

Commissioner

J. LEONARD LEDBETTER

Site Name and Location: American Metals Company, Inc. (4)
1150 Marietta Industrial Drive, N.E.
Marietta, Georgia 30062

Trip By: Frances M. Hallahan *FH*

Accompanied By: None

Date of Trip: January 16, 1985; 1:30 p.m.; cloudy, cold.

Officials Contacted: Mr. Carl H. Patton, Plant Superintendent
(404)427-9471

Mr. Carl Hauser, Facility Engineer

Reference: Complaint #5-136

Comments:

1. Process: This facility paints large rolls of steel sheeting which is then shipped elsewhere for fabrication. They are technically described as a "coil coater". The steel rolls are uncoiled and fed through the following steps:

- a) Caustic wash, which removes the oil coating on the steel
- b) Water rinse
- c) Iron phosphate pre-treatment
- d) Water rinse
- e) Final rinse in a weak solution of chromic acid
- f) Prime and/or finish coat of paint. If the prime coat contains chrome ;
- g) Oven bake to cure the paint
- h) Cooled
- i) Re-coiled and packed for shipment
- j) Some coils are cut to smaller sizes after coating

The paint is applied with rollers, so there is no paint overspray waste. Solvents are used to clean the rolls, and about 80 drums of spent solvents are generated every 90 days. These are appropriately manifested as a hazardous waste to Arivec Chemicals.

All washwater, rinses and spent baths, and bottom sludges are fed to the wastewater treatment system. The officials admitted that this system has not been working properly since they located here in 1980. At present, all wastewater treatment is shut down completely, and the waste stream is fed untreated to the city sewer connection. The officials explained that the city is aware of this discharge, and they are allowed to discharge until the wastewater treatment system becomes operative, with in about 6 weeks. This untreated discharge is probably the basis of the complaint by an anonymous employee. The new system will consist of:

AN AFFIRMATIVE ACTION/EQUAL EMPLOYMENT OPPORTUNITY EMPLOYER

FILE COPY

- a) Chrome treatment with sodium metabisulfite
- b) Oil skim
- c) pH adjustment
- d) Clarifier
- e) Filter press
- f) Discharge of effluent to city sewer

The filter press sludge will be hazardous because of the chrome content. The sludge will also be high in zinc hydroxide because the caustic bath draws the zinc from the steel to form zinc hydroxide.

2. Plant Tour

General plant housekeeping was good. The 3-stage washer is self contained, and solvent handling in the paint room is satisfactory, except that the spent solvents are not labelled at the point of generation. At the time of this inspection, a tanker truck from Arivec was in the process of pumping out about 40 drums of paint/solvent waste. These drums were also not labelled and dated. The officials explained that these drums would be used over again to collect more waste. Empty drums of fresh solvent, the iron phosphate, and chrome, are recycled back to suppliers at the time of delivery.

The facility generates about 1 drum every 3 months of waste motor oil from the fork lifts in the plant. We agreed that the oil would be tested for hazardousness.

Inspection of the outside clarifier revealed 7 drums of sludge which were generated when the old wastewater treatment system was in operation. These were unlabelled and uncovered, and officials admitted that they had been accumulating for over 90 days.

3. Wastes Generated:

- a) Spent paint solvents - about 80 drums/3 months
- b) Wastewater treatment sludge - hazardous
- c) oil to be skimmed from wastewater treatment
- d) Waste motor oil.

4. Examination of Paperwork:

Manifests for spent solvents were in order, and reflect shipment within the 90 day period. There is no inspection program for the hazardous wastes, and the facility has no Preparedness and Prevention Plan, Contingency Plan or Personnel Training Program.

Conclusions: Facility is in violation of:

40 CFR 262.11 "Determination", because waste oil has not been identified as hazardous or non-hazardous;

Page Three (3)
TR-American Metals Company, Inc.

40 CFR 262.34(a) "Accumulation Time", because 7 drums of sludge have been stored over 90 days, and because both sludge and paint solvent waste are not marked "Hazardous Waste", and are not marked with beginning dates of accumulation;

40 CFR 262.34(a)(4) "Accumulation Time", because the facility has no Preparedness and Prevention Plan, Contingency Plan, or Personnel Training Program.

40 CFR 265, Subpart I, "Containers", because some containers of hazardous waste are not kept in good condition and are uncovered, and because there is no weekly inspection of containers.

Recommendations and follow-up Required: Send NOV.

Photographs: None

Reviewed By:

George Morris 2-12-85

Attachments: Copy of Complaint

FH:djb:005

cc: Frances Hallahan
Complaint Log #5-136
Howard Barefoot

File: American Metals Co. (R)



POTENTIAL HAZARDOUS WASTE SITE
TENTATIVE DISPOSITION

REGION SITE NUMBER
IV GAD 0008 278 73

File this form in the regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency, Site Tracking System, Hazardous Waste Enforcement Task Force (EN-335), 401 M St., SW, Washington, DC 20460.

I. SITE IDENTIFICATION

A. SITE NAME
American Metals Company

B. STREET
1150 Marietta Ind Blvd.

C. CITY
Marietta

D. STATE
GA

E. ZIP CODE
30060

II. TENTATIVE DISPOSITION

Indicate the recommended action/s and agency/ies that should be involved by marking 'X' in the appropriate boxes.

RECOMMENDATION	MARK 'X'	ACTION AGENCY			
		EPA	STATE	LOCAL	PRIVATE
A. NO ACTION NEEDED - NO HAZARD					
B. INVESTIGATIVE ACTION'S NEEDED (If yes, complete Section III.)	X	X			
C. REMEDIAL ACTION NEEDED (If yes, complete Section IV.)					
D. ENFORCEMENT ACTION NEEDED (If yes, specify in Part E whether the case will be primarily managed by the EPA or the State and what type of enforcement action is anticipated.)					

E. RATIONALE FOR DISPOSITION

Low priority per state PA. Unknown waste handling practices prior to 1980. Sludges stored in drums on site. Part A withdrawn.

CERCLIS entry date 850622

F. INDICATE THE ESTIMATED DATE OF FINAL DISPOSITION (mo., day, & yr.)

G. IF A CASE DEVELOPMENT PLAN IS NECESSARY, INDICATE THE ESTIMATED DATE ON WHICH THE PLAN WILL BE DEVELOPED (mo., day, & yr.)

H. PREPARER INFORMATION

1. NAME
Camilla Bond Warren

2. TELEPHONE NUMBER
FTS 251-2234

3. DATE (mo., day, & yr.)
6/27/85

III. INVESTIGATIVE ACTIVITY NEEDED

A. IDENTIFY ADDITIONAL INFORMATION NEEDED TO ACHIEVE A FINAL DISPOSITION.

*Recon Site
Sampling*

B. PROPOSED INVESTIGATIVE ACTIVITY (Detailed Information)

1. METHOD FOR OBTAINING NEEDED ADDITIONAL INFO.	2. SCHEDULED DATE OF ACTION (mo., day, & yr.)	3. TO BE PERFORMED BY (EPA, Contractor, State, etc.)	4. ESTIMATED MANHOURS	5. REMARKS
a. TYPE OF SITE INSPECTION				
(1) _____	_____	_____	_____	_____
(2) _____	_____	_____	_____	_____
(3) _____	_____	_____	_____	_____
b. TYPE OF MONITORING				
(1) _____	_____	_____	_____	_____
(2) _____	_____	_____	_____	_____
c. TYPE OF SAMPLING				
(1) _____	_____	_____	_____	_____
(2) _____	_____	_____	_____	_____

III. INVESTIGATIVE ACTIVITY NEEDED and PART B. PROPOSED INVESTIGATIVE ACTIVITY (Continued)

d. TYPE OF LAB ANALYSIS				
(1) _____				
(2) _____				
e. OTHER (specify)				
(1) _____				
(2) _____				

c. ELABORATE ON ANY OF THE INFORMATION PROVIDED IN PART B (on front & above), AS NEEDED TO IDENTIFY ADDITIONAL INVESTIGATIVE WORK.

d. ESTIMATED MANHOURS BY ACTION AGENCY

1. ACTION AGENCY	2. TOTAL ESTIMATED MANHOURS FOR INVESTIGATIVE ACTIVITIES	1. ACTION AGENCY	2. TOTAL ESTIMATED MANHOURS FOR INVESTIGATIVE ACTIVITIES
a. EPA		b. STATE	
c. EPA CONTRACTOR		d. OTHER (specify)	

IV. REMEDIAL ACTIONS

A. SHORT TERM EMERGENCY STRATEGY (On Site & Off-Site) List all emergency actions needed to bring site under immediate control, e.g., restrict access, provide alternate water supply, etc. See instructions for a list of Key Words for each of the actions to be used in the space below.

1. ACTION	2. EST. START DATE (mo, day, & yr)	3. EST. END DATE (mo, day, & yr)	4. ACTION AGENCY (EPA, State, Private Party)	5. ESTIMATED COST	6. SPECIFY 311 OR OTHER ACTION; INDICATE THE MAGNITUDE OF THE WORK REQUIRED
				\$	
				\$	
				\$	
				\$	
				\$	
				\$	

B. LONG TERM STRATEGY (On Site & Off-Site) List all long term solutions, e.g., excavation, removal, ground water monitoring wells, etc. See instructions for a list of Key Words for each of the actions to be used in the spaces below.

1. ACTION	2. EST. START DATE (mo, day, & yr)	3. EST. END DATE (mo, day, & yr)	4. ACTION AGENCY (EPA, State, Private Party)	5. ESTIMATED COST	6. SPECIFY 311 OR OTHER ACTION; INDICATE THE MAGNITUDE OF THE WORK REQUIRED
				\$	
				\$	
				\$	
				\$	
				\$	
				\$	

c. ESTIMATED MANHOURS AND COST BY ACTION AGENCY

1. ACTION AGENCY	2. TOTAL EST. MANHOURS FOR REMEDIAL ACTIVITIES	3. TOTAL EST. COST FOR REMEDIAL ACTIVITIES	1. ACTION AGENCY	2. TOTAL EST. MANHOURS FOR REMEDIAL ACTIVITIES	3. TOTAL EST. COST FOR REMEDIAL ACTIVITIES
a. EPA			b. STATE		
c. PRIVATE PARTIES			d. OTHER (specify)		

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 44
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - SITE MAINTENANCE FORM

		* ACTION: _	*
EPA ID : GAD000827873			
SITE NAME: AMERICAN METALS COMPANY INC	SOURCE: H	* _____	*
STREET : 1150 MARIETTA IND BLVD	CONG DIST: 07	* _____	*
CITY : MARIETTA	ZIP: 30060	* _____	*
CNTY NAME: COBB	CNTY CODE : 067	* _____	*
LATITUDE : 34/37/59.0	LONGITUDE : 084/32/30.0	* __/__/__.	*
LL-SOURCE: R	LL-ACCURACY:	* _	*
SMSA : 0520	HYDRO UNIT: 03130002	* _____	*
INVENTORY IND: Y	REMEDIAL IND: Y	REMOVAL IND: N	FED FAC IND: N
NPL IND: N	NPL LISTING DATE:	NPL DELISTING DATE:	
SITE/SPILL IDS:			
RPM NAME: RAY WILKERSON	RPM PHONE: 404-347-2234	* _____	*
SITE CLASSIFICATION:	SITE APPROACH:	* _	*
DIOXIN TIER:	REG FLD1:	REG FLD2: 6	* _____
RESP TERM: PENDING ()	NO FURTHER ACTION ()	* PENDING ()	NO FURTHER ACTION ()
ENF DISP: NO VIABLE RESP PARTY ()	VOLUNTARY RESPONSE ()	* _	_
ENFORCED RESPONSE ()	COST RECOVERY ()	* _	_
SITE DESCRIPTION:			
FACILITY ENGAGED IN PAINTING STEEL SHEETING.			
* _____			
* _____			
* _____			
* _____			

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 45
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - ALIAS/ALIAS LOCATION MAINTENANCE FORM

SITE: AMERICAN METALS COMPANY INC

EPA ID: GAD000827873

ALIAS SEQ NO: 01

ALIAS NAME: PRIOR COATED METALS, INC

SOURCE: R

* ACTION: _

ALIAS LOCATION

CONTIGUOUS PORTION OF SITE?

FED FAC IND:

STREET :

CONG DIST :

CITY :

ST:

ZIP:

CNTY NAME:

CNTY CODE:

LATITUDE : / /

LONGITUDE : / /

LL-SOURCE:

LL-ACCURACY:

SMSA :

HYDRO UNIT:

* ACTION: _

* _

* _

* _

* _

* _/_/_

* _

* _

ALIAS DESCRIPTION:

* _

* _

* _

* _

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 46
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - PROGRAM MAINTENANCE FORM

SITE: AMERICAN METALS COMPANY INC

EPA ID: GAD000827873 PROGRAM CODE: H01 PROGRAM TYPE:

PROGRAM QUALIFIER: ALIAS LINK :

PROGRAM NAME: SITE EVALUATION

DESCRIPTION:

* ACTION: _

*

*

*

*

*

*

*

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 47
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - EVENT MAINTENANCE FORM

* ACTION: _

SITE: AMERICAN METALS COMPANY INC
PROGRAM: SITE EVALUATION

EPA ID: GAD000827873 PROGRAM CODE: H01

EVENT TYPE: DS1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: E

EVENT NAME: DISCOVERY

STATUS:

DESCRIPTION:

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

* _ _ _ _ _ *

ORIGINAL

CURRENT

ACTUAL

START:

START:

START:

* _/_/_/_ _/_/_/_ _/_/_/_ *

COMP :

COMP :

COMP : 08/01/80

* _/_/_/_ _/_/_/_ _/_/_/_ *

HQ COMMENT:

* _ _ _ _ _ *

RG COMMENT:

* _ _ _ _ _ *

COOP AGR #

AMENDMENT #

STATUS

STATE %

0

* _ _ _ _ _ *

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 48
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - EVENT MAINTENANCE FORM

* ACTION: _

SITE: AMERICAN METALS COMPANY INC
PROGRAM: SITE EVALUATION

EPA ID: GAD000827873 PROGRAM CODE: H01 EVENT TYPE: PA1

FMS CODE: EVENT QUALIFIER : EVENT LEAD: S

EVENT NAME: PRELIMINARY ASSESSMENT STATUS:

DESCRIPTION:

LOW PRIORITY. UNKNOWN WASTE HANDLING PRACTICES PRIOR TO
1980. RCRA PART A WITHDRAWN.

ORIGINAL	CURRENT	ACTUAL
START:	START:	START: 06/27/85
COMP :	COMP :	COMP : 06/27/85

HQ COMMENT:

RG COMMENT:

COOP AGR #	AMENDMENT #	STATUS	STATE X
			0

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 49
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - COMMENT MAINTENANCE FORM

SITE: AMERICAN METALS COMPANY INC

EPA ID: GAD000827873

COM
NO COMMENT

001 PART A- ON FILE

ACTION

*

-

*

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 44
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - SITE MAINTENANCE FORM

EPA ID : GAD000827873		* ACTION: _
SITE NAME: AMERICAN METALS COMPANY INC	SOURCE: H	* _____
STREET : 1150 MARIETTA IND BLVD	CONG DIST: 07	* _____
CITY : MARIETTA	ZIP: 30060	* _____
CNTY NAME: COBB	CNTY CODE : 067	* _____
LATITUDE : 34/37/59.0	LONGITUDE : 084/32/30.0	* _/_/_.
LL-SOURCE: R	LL-ACCURACY:	* _
SMSA : 0520	HYDRO UNIT: 03130002	* _____
INVENTORY IND: Y	REMEDIAL IND: Y	* _
REMOVAL IND: N	FED FAC IND: N	* _
NPL IND: N	NPL LISTING DATE:	* _/_/_
NPL DELISTING DATE:		* _/_/_
SITE/SPILL IDS:		* _ _ _ _
RPM NAME: RAY WILKERSON	RPM PHONE: 404-347-2234	* _____
SITE CLASSIFICATION:	SITE APPROACH:	* _
DIOXIN TIER:	REG FLD1:	* _
	REG FLD2: 6	* _
RESP TERM: PENDING ()	NO FURTHER ACTION ()	* PENDING () NO FURTHER ACTION ()
ENF DISP: NO VIABLE RESP PARTY ()	VOLUNTARY RESPONSE ()	* _
ENFORCED RESPONSE ()	COST RECOVERY ()	* _
SITE DESCRIPTION:		
FACILITY ENGAGED IN PAINTING STEEL SHEETING.		* _____
		* _____
		* _____
		* _____

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 45
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - ALIAS/ALIAS LOCATION MAINTENANCE FORM

SITE: AMERICAN METALS COMPANY INC

EPA ID: GAD000827873

ALIAS SEQ NO: 01

ALIAS NAME: PRIOR COATED METALS, INC

SOURCE: R

ALIAS LOCATION

CONTIGUOUS PORTION OF SITE?

FED FAC IND:

STREET :

CONG DIST :

CITY :

ST: ZIP:

CNTY NAME:

CNTY CODE:

LATITUDE : / /

LONGITUDE : / /

LL-SOURCE:

LL-ACCURACY:

SMSA :

HYDRO UNIT:

ALIAS DESCRIPTION:

* ACTION: -

* ACTION: -

* -

* -

* -

* -

* -

* -

* -

* -

* -

* -

* -

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 46
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - PROGRAM MAINTENANCE FORM

* ACTION: _

SITE: AMERICAN METALS COMPANY INC

EPA ID: GAD000827873 PROGRAM CODE: M01 PROGRAM TYPE:

PROGRAM QUALIFIER: ALIAS LINK :

PROGRAM NAME: SITE EVALUATION

DESCRIPTION:

* _____

* _____

* _____

* _____

* _____

* _____

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 47
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - EVENT MAINTENANCE FORM

* ACTION: _

SITE: AMERICAN METALS COMPANY INC
PROGRAM: SITE EVALUATION

EPA ID: GAD000827873 PROGRAM CODE: H01

EVENT TYPE: DSI

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: E

EVENT NAME: DISCOVERY

STATUS:

DESCRIPTION:

* _
* _
* _
* _
* _

ORIGINAL

CURRENT

ACTUAL

START:

START:

START:

* _/_/_ _/_/_ _/_/_

COMP :

COMP :

COMP : 08/01/80

* _/_/_ _/_/_ _/_/_

HQ COMMENT:

* _

RG COMMENT:

* _

COOP AGR #

AMENDMENT #

STATUS

STATE %

* _

0

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 48
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - EVENT MAINTENANCE FORM

* ACTION: _

SITE: AMERICAN METALS COMPANY INC
PROGRAM: SITE EVALUATION

EPA ID: GAD000827873 PROGRAM CODE: W01 EVENT TYPE: PA1

FMS CODE: EVENT QUALIFIER : EVENT LEAD: S

EVENT NAME: PRELIMINARY ASSESSMENT STATUS:

DESCRIPTION:

LOW PRIORITY. UNKNOWN WASTE HANDLING PRACTICES PRIOR TO
1980. RCRA PART A WITHDRAWN.

ORIGINAL	CURRENT	ACTUAL
START:	START:	START: 06/27/85
COMP :	COMP :	COMP : 06/27/85

HQ COMMENT:

RG COMMENT:

COOP AGR # AMENDMENT # STATUS STATE X

0

REGION: 04
STATE : GA

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

PAGE: 49
RUN DATE: 01/30/87
RUN TIME: 08:18:49

M.2 - COMMENT MAINTENANCE FORM

SITE: AMERICAN METALS COMPANY INC

EPA ID: GAD000827873

COM
NO COMMENT

001 PART A- ON FILE

ACTION

-